



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 वेबसाइट : www.kgmu.org

पत्रांक: 1674/M10

दिनांक: 04/12/2023

QUOTATION NOTICE

To,
M/s.....
.....
.....

The sealed quotations are invited for repairing of damaged floor tiles, wall tiles and aluminum doors and other misc. work in Shatabdi hospital phase-1&2 at kgmu the detail of quotation notice can be seen at website www.kgmu.org and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 08/12/2023.....

Details of the work as given below-

| Sl.No. | Particulars | Qty. | Unit | Rate |
|--------|--|-------|------|------|
| 1. | Dismantling cement concrete or granolithic floors, including stacking of dismantling material as per direction by the E/I. | 27.12 | Sqm | |
| 2. | P/L cement concrete in 1:2:4 cement, coarse sand 20mm stone grit. | 1.15 | Cum | |
| 3. | P/L floor tiles in size 300x300mm with water absorption less then 0.08% and conforming to IS: 15622 of approved make in all colours and sheds laid on 20mm thick cement mortar in 1:4 including grouting of joints with white cement and matching pigment etc. complete. | 27.12 | Sqm | |
| 4. | P/L 18mm thick black granite in required design and pattern with 1:4 cement coarse sand including all labour material etc. complete. | 0.78 | Sqm | |
| 5. | Providing edge moulding to 18 mm thick marble stone counters, Vanities etc., including machine polishing to edge to give high gloss finish etc. complete. | 2.40 | Rmt | |
| 6. | Providing labour charge for repairing of old aluminum door. | 49.59 | Sqm | |
| 7. | P/L G.I metal false ceiling lay in perforated tegular edge global white color tiles of size 595x595 mm and 0.5mm thick with 8mm drop including all labour material t&p etc. including factory painted after bending. | 2.88 | Sqm | |
| 8. | Providing and fixing false ceiling with 12.5 mm thick tapered edge gypsum moisture resistant board conforming to IS: 2095. including all materials, labours, T&P complete etc. | 2.14 | Rmt | |
| 9. | P/F 12mm thick frameless toughened glass door shutter of appd brand and manufacture, including providing and fixing top and bottom pivot & double acting hydraulic floor spring type fixing arrangement and making necessary holes etc. | 1.33 | Sqm | |
| 10. | Providing & fixing 5mm thick glass panes with glazing doors, windows, ventilators, shutter and partition etc. with EPDM rubber/ neopren gasket etc. complete as per direction in charge | 2.69 | Sqm | |
| 11. | Supply and fixing anodised aluminum butt hinges 125x75x4mm. | 30.00 | Nos | |
| 12. | P/F of aluminum tower bolt 150mm long. | 04 | Nos | |
| 13. | Providing and fixing floor door stopper. | 04 | Nos | |
| 14. | Providing and laying cement based white putty of average thickness 0.60mm of approved brand and manufacture, over the old painted wall surface to prepare the surface even and smooth complete. | 11.15 | Sqm | |
| 15. | Distempering with oil bound distemper two coat of approved brand old surface to give an even shade including all material, labour T&P etc. complete. | 11.15 | Sqm | |
| 16. | Cartage for disposal of malwa up to 10km away from site. | 1.95 | Cum | |

JKay
JEI



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 वेबसाइट : www.kgmu.org

पत्रांक: -----



दिनांक:-----

| | | | | |
|-----|---|----|-----|--|
| 17. | Providing labour charge for cleaning of roof and collecting malwa | 02 | Nos | |
|-----|---|----|-----|--|

Terms & Conditions.

1. G.S.T & Labour Cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully


(Suresh Kumar) 
Executive Engineer Superintendent Engineer


JE

No...../ of DT.

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date 04/12/2023.. To 08/12/2023
3. Sri T.C Yadav, Assistant Engineer, Works deptt. K.G.M.U.U.P.Lucknow
4. Sri Poshit Roy, Junior Engineer, Works deptt. K.G.M.U.U.P.Lucknow
5. Notice Board.


(Suresh Kumar) 
Executive Engineer Superintendent Engineer


JE