



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 वेबसाइट : www.kgmu.org

पत्रांक: -----

2240/M10

QUOTATION NOTICE

दिनांक:.....

11/03/2024

To,

M/s.....

.....

.....

The sealed quotations are invited for shifting of aluminum partition, repairing of old damaged floor tiles, repairing of damage water pipe line and other misc. work in Shatabdi hospital phase-I kgmu the detail of quotation notice can be seen at website www.kgmu.org and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated

18/03/2024
Details of the work as given below-

Sl.No.	Particulars	Qty.	Unit	Rate
1	Dismantling damaged floors tiles including stacking of dismantling material as per direction by the E/I	6.12	Sqm	
2	Dismantling existing old plaster including disposal of refuse as directed by Engineer-in-charge	2.54	Sqm	
3	P/L cement concrete in 1:2:4 cement, coarse sand 20mm stone grit.	0.34	Cum	
4	M-150 class 230mm thick brick work in 1:4 cement & coarse sand in super structure including supply of all materials, labours and T&P etc. for proper completion of the work	0.22	Cum	
5	P/L pavit floor tiles in size 300x300 x9mm of approved make in all colours and sheds layd on 20mm thick base of 1:4 cement coarse sand in all complete.	4.50	Sqm	
6	P/L floor tiles in size 300x300mm of approved make in all colours and sheds , laid on 1:4 cement coasre sand including grouting of joints with white cement and matching pigment etc. complete	2.57	Sqm	
7	P/L wall tiles 300x600mm with of approved make in all colours and sheds, laid on 12mm thick cement mortar in 1:3 cement coarse sand including grouting of joints with white cement and matching pigment.	2.54	Sqm	
8	P/L 18mm thick black granite in required design and pattern with 1:4 cement coarse sand including all labour material etc. complete.	0.25	Sqm	
9	Providing edge moulding to 18 mm thick marble stone counters, Vanities etc., including machine polishing to edge to give high gloss finish etc. complete.	3.10	Rmt	
10	Providing labour charge for repairing of old aluminum door.	37.78	Sqm	
11	P/F anodised aluminum work for partitions with extruded built up standerd tubular section Z section and other section of approved make comforming to IS: 733 and is: 1285 fixing with dash fasteners of required dia size including necessary fittings up the gaps at junctions I.E at top, bottom, and sides with required EPDM rubber/ neoprene gasket etc. complete.	9.31	Kg	
12	P/F rubber beading for fixing of glass in aluminum door and parttion.	16.82	Rmt	
13	P/F aluminum clip for fixing of glass in aluminum door and parttion.	2.28	Rmt	
14	Providing & fixing 5mm thick glass panes with glazing doors, windows, ventilators, shutter and parttion etc. with EPDM rubber/ neopren gasket etc. complete as per direction in charge	1.13	Sqm	
15	S/F ACP sheet in palce of plain glass.	2.34	Sqm	



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 वेबसाइट : www.kgmu.org

पत्रांक: -----

दिनांक:

16	P/F transparent film of appd quality on glass including labour material complete	3.94	Sqm	
17	S/F door closer for appd quality godrej or equivalent.	04	Nos	
18	Supply and fixing anodised aluminum butt hinges 125x75x4mm.	16.00	Nos	
19	P/F of aluminum tower bolt 150mm long	02	Nos	
20	P/F american handle 150mm long	04	Nos	
21	Painting two coats with Superior synthetic enamel paint in old Surface including supply of labour material t&p etc. complete.	16.69	Sqm	
22	Repairing of old false ceiling and new grid including all complete fittings.	11.52	Sqm	
23	P/F hydraulic seat cover make appd quality	02	Nos	
24	P/F G.I Tee 15mm dia	02	No	
25	P/F PTMT bib cock 15mm dia	02	Nos	
26	S/F C.P floor jaali 110mm dia.	02	Nos	
27	S/F wash basin white glazed 22"x16" complete with pillar cock, bracket, waste jali, waste pipe, PVC connection etc	02	Nos	
28	S/F of white glazed Orissa Pan 580 mm dia with hepco red C.I traps 100mm dia	01	No.	
29	P/F White glazed (European type) W.C pan 505mm dia with seat cover of jaguar ESSCO, cera hindware.	01	No.	
30	S/F 10 Lit PVC low down cistern for appd. Quality in completed.	01	No	
31	P/F 600x450mm beveled edge mirror of superior glass complete with 6mm thick hard board fixed to wooden cleats with C.P. brass screws and washers complete	01	No.	
32	P/F brass gate valve 25mm dia make of NMV	01	No.	
33	S/F PVC connection 600mm long Prayag make.	02	Nos	
34	Providing Sweeper for cleaning of mainhole and sewer line by sweeper with tools including disposal of garbage as per direction of site incharge	01	No.	
35	S/F C.P Angle valve 15mm dia. make of appd quality.	02	Nos	
36	Providing Plumber with helper for repairing of old fitting and making water connections	01	No	
37	S/F C.P health faucet with c.p lead 1.5m. for appd. quality.	01	No.	
38	Providing labour for cleaning of site and collecting malwa	02	Nos	

Terms & Conditions.

1. G.S.T & Labour Cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully


(Suresh Kumar) 
(Dinesh Kumar Raj)
Executive Engineer Superintendent Engineer

No. 2240/MC of DT.


R. Roy
TE



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

निर्माण विभाग


फोन (कुलसचिव कार्यालय) : 0522-2257540 वेबसाइट : www.kgmu.org


पत्रांक: -----

दिनांक:.....

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date. 11/03/24 To. 18/03/24
3. Sri T.C.Yadav, Assistant Engineer, Works deptt. K.G.M.U.U.P.Lucknow
4. Sri Poshit Roy, Junior Engineer, Works deptt. K.G.M.U.U.P.Lucknow
5. Notice Board.


(Suresh Kumar)
Executive Engineer


(Dinesh Kumar Raj)
Superintendent Engineer


JE