



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 वेबसाइट : www.kgmu.org

पत्रांक: 1635/M-10/2023

दिनांक: 08/11/23

**QUOTATION NOTICE**

To,

M/s.....

The sealed quotations are invited Repair of old aluminum door and other misc. work at ground and first floor in Shatabdi hospital phase-1 kgmu the detail of quotation notice can be seen at website [www.kgmu.org](http://www.kgmu.org) and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 04/11/2023.

Details of the work as given below-

| Sl.No. | Particulars  | Qty.  | Unit | Rate |
|--------|--|-------|------|------|
| 1.     | Dismantling existing old plaster including disposal of refuse as directed by engineer incharge.  | 0.35  | Sqm  |      |
| 2.     | Dismantling cement concrete or granolithic floors, including stacking of dismantling material as per direction by the E/I.   | 4.32  | Sqm  |      |
| 3.     | P/L cement concrete in 1:2:4 cement, coarse sand 20mm stone grit.  | 0.35  | Cum  |      |
| 4.     | P/L 18mm thick black granite in required design and pattern with 1:4 cement coarse sand including all labour material etc. complete  | .35   | Sqm  |      |
| 5.     | P/L floor tiles in size 600x600mm with water absorption less then 0.08% and conforming to IS: 15622 of approved make in all colours and sheds laid on 20mm thick cement mortar in 1:4 including grouting of joints with white cement and matching pigment etc. complete. | 4.32  | Sqm  |      |
| 6.     | Providing edge moulding to 18 mm thick marble stone counters, Vanities etc., including machine polishing to edge to give high gloss finish etc. complete.  | 3.90  | Rmt  |      |
| 7.     | Providing labour charge for repairing of old aluminum door.  | 35.11 | Sqm  |      |
| 8.     | P/F G.I metal tile clip in plin beveled edge global white colour tile size 600x600mm nd 0.5mm thick.   | 2.16  | Sqm  |      |
| 9.     | S/F ACP sheet in palce of plain glass.   | 4.82  | Sqm  |      |
| 10.    | Providing & fixing 5mm thick glass panes with glazing doors, windows, ventilators, shutter and partition etc. with EPDM rubber/ neopren gasket etc. complete as per direction in charge  | 2.99  | Sqm  |      |
| 11.    | Supply and fixing anodised aluminum butt hinges 125x75x4mm.  | 18.00 | Nos  |      |
| 12.    | P/F of aluminum tower bolt 150mm long.   | 03    | Nos. |      |
| 13.    | Providing and fixing floor door stopper.   | 02    | Nos. |      |
| 14.    | S/F C.P two way bib cock heavy quality short body with wall flang.   | 01    | No.  |      |
| 15.    | Cartage for disposal of malwa up to 10km away from site.   | 4.21  | Cum  |      |
| 16.    | Providing labour for cleaning of site and collecting malwa   | 9.00  | Nos  |      |

Terms & Conditions.

1. G.S.T & Labour Cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotations are liable to be rejected.

T. Ray  
JE



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

निर्माण विभाग


फोन (कुलसचिव कार्यालय) : 0522-2257540 वेबसाइट : www.kgmu.org

पत्रांक: -----

दिनांक:.....

5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully

  
(Suresh Kumar) (Dinesh Kumar Raj)  
Executive Engineer Superintendent Engineer

Def No-1635/M-10/2023

No...../ of DT. 28/11/2023

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date.. 28/11/2023 To.. 09/12/2023
3. Sri T.C Yadav, Assistant Engineer, Works deptt. K.G.M.U.U.P.Lucknow
4. Sri Poshit Roy, Junior Engineer, Works deptt. K.G.M.U.U.P.Lucknow
5. Notice Board.

  
(Suresh Kumar) (Dinesh Kumar Raj)  
Executive Engineer Superintendent Engineer

  
T. Roy  
JE