



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 ई-मेल : eng.civil@kgmcindia.edu

पत्रांक: -----

1773 / M1c

QUOTATION NOTICE

दिनांक:

21/12/2023

To,

M/s.....

.....

.....

The sealed quotations are invited for Construction of drain near parking including fabrication of m.s. gate on first floor and other misc. work at nehru hostel KGMU. The details of quotation notice can be seen at website www.kgmu.org and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 28/12/2023

Details of work as given below:-

S.No.	Particulars	Quantity	Unit	Rate
1.	Fabrication of M.S frame stucture with hollow pipe including labour material t&p complete.	174.94	Kg.	
2.	Painting 2 coats with supirior synthetic enamel paint on new surface with one coat primer upto 10 cm width or grith.	11.50	Sqm.	
3.	P/F carbon steel galvanised dash fastener of 10mm dia 80mm long including drilling of hole in frame, concrete/ masonry,etc. as per direction of E/I.	08	Nos.	
4.	P/F ISI marked oxidised M.S. butt hinges 125mm complete.	08	Nos.	
5.	P/F ISI marked oxidised M.S. sliding door bolt of size 300X16mm with nuts and screws complete.	01	No.	
6.	P/F ISI marked oxidised M.S. handles 125mm complete.	02	Nos.	
7.	Taking out existing CC interlocking paver blocks from footpath/ central verge, including removal of rubbish etc., disposal of unserviceable material to the dumping ground, for which payment shall be made separately and stacking of serviceable material within 50 metre lead as per direction of Engineer-in-Charge.	23.38	Sqm.	
8.	Earth work in excavation in trenches for foundations in ordinary soil including lift upto 1.5 m. lead upto 50m and dressing of sides and rammings of bottom.	3.15	Cum.	
9.	M-150 Class brick work in 1:4 cement coarse sand in foundation including supply of all materials, labours and T&P etc.for proper completion of the work.	1.54	Cum.	
10.	P/L PCC 1:5:8 cement, fine sand & 40mm stone ballast.	0.75	Cum.	
11.	P/L cement concrete in 1:2:4 cement ,coarse sand 20mm stone grit.	0.71	Cum.	
12.	P/L Vitrified wall tiles 300x600mm with water absorption less then 0.08% and conforming to IS: 15622 of approved make in all colours and sheds , laid on 12mm thick cement mortar in 1:3 cement coarse sand including grouting of jointes with white cement and matching pigment.	1.44	Sqm.	
13.	P/L 12mm cement plaster in 1:3 (1 Cement :3Coarse sand) finished with a floating coat of neat cement.	22.82	Sqm.	
14.	Providing and fixing 1.00mm thick solid pvc sheet of approved make including material, labour T&P complete.	9.72	Sqm.	

1773 / M1c



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003 निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 ई-मेल : eng.civil@kgmcindia.edu

पत्रांक: -----

दिनांक:

15.	P/F PVC pipe 100mmdia. 6kg pressure make of approved quality complete.	8.90	Rmt.	
16.	Providing Carpenter with helper for repairing of old door/window.	06	Nos.	
17.	Providing welder with welding machine for repairing and refixing.	02	Nos.	
18.	Providing labour for cleaning of site and shifting of material.	06	Nos.	

Terms & Conditions

1. G.S.T and labour cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully


(Suresh Kumar)
Executive Engineer


(Dinesh Kumar Raj)
Superintending Engineer


T. Ray
JE

No. 1773/M1e / of DT.

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date 21/12/2023 To 28/12/2023
3. Sri T.C. Yadav, Assistant Engineer, Works deptt. K.G.M.U. U.P. Lucknow
4. Sri Poshit roy, Junior Engineer, Works deptt. K.G.M.U. U.P. Lucknow
5. Notice Board.


(Suresh Kumar)
Executive Engineer


(Dinesh Kumar Raj)
Superintending Engineer


T. Ray
JE