



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 वेबसाइट : www.kgmu.org

पत्रांक: ----- 2235/MC

दिनांक:

22/3/24
22/3/2024

QUOTATION NOTICE

To,
M/s.....
.....
.....

The sealed quotations are invited for P/L C.C work and other misc. work in front of pediatric department; kalam cenetr side work at kgmu.the detail of quotation notice can be seen at website www.kgmu.org and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated

Details of the work as given below-

Sl.No.	Particulars	Qty.	Unit	Rate
1.	M-150 Class 230mm thick brick work in 1:4 cement coarse sand in foundation including supply of all materials, labours and T&P etc.for proper completion of the work.	4.69	Cum	
2.	P/L 12mm thick cement plaster in 1:6 on wall with cement and coarse sand including supply of all material labour and T&P etc. for proper completion of work.	45.00	Sqm	
3.	15mm cement plaster 1:3 cement coarse sand finishing with a floating coat of neat cement.	4.32	Sqm	
4	P/L cement concrete in 1:2:4 cement, coarse sand 20mm stone grit.	1.34	Cum	
5	P/L PCC 1:6:12 cement, fine sand& 40mm brick ballast.	0.71	Cum	
6	laying old cement concrete interlocking paver block of any design shape laid in over 50mm thick compacted bed of coarse sand filling the jointes with fine sand etc. all complete.	8.92	Sqm	
7	Mild steel work for reinforcement in plain cement concrete including binding, bending and cutting complete.	25.11	Kg	
8	P/L RCC work in cover in 1:1.5:3 cement, coarse sand and stone aggregate	0.13	Cum	
9	S/F of C.I pipe 100mm dia HEPCO make	3.15	Rmt	
10	S/F C.I Plain bend 100mm dia HEPCO make	02	Nos	
11	S/F of C.I collar 100m dia. HEPCO make.	02	Nos	
12	Applying one coat white cement on new surface.	45.00	Sqm	
13	Providing and laying white cement based putty of average thickness 1mm of approved band on new surface.	45.00	Sqm	
14	Application of two coats apex Ultima paint on outer surface including supply of all materials, labours and T&P etc. for proper completion of the work.	45.00	Sqm	
15	Providing Sweeper for cleaning of mainhole and sewer line by sweeper with tools including disposal of garbage as per direction of site incharge	03	No.	



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003 निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 वेबसाइट : www.kgmu.org


पत्रांक: -----


16	Providing labour for cleaning of site and collecting malwa	02	Nos.	दिनांक:.....
----	------------------------------------------------------------	----	------	--------------

Terms & Conditions.

1. G.S.T & Labour Cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully



(Shailendra Singh)
Executive Engineer



(Dinesh Kumar Raj)
Superintendent Engineer

No. 2236/M/10 of DT.

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date 27/03/2024 To 14/03/2024
3. Sri Anjani Kumar, Assistant Engineer, Works deptt. K.G.M.U.U.P.Lucknow
4. Sri Prateek Dubey, Junior Engineer, Works deptt. K.G.M.U.U.P.Lucknow
5. Notice Board.


(Shailendra Singh)
Executive Engineer


(Dinesh Kumar Raj)
Superintendent Engineer

