



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2253171 Email eng.civil@kgmcindia.edu

पत्रांक: -----

2103/M10

QUOTATION NOTICE

दिनांक:

08/02/2024

To,

M/s.....

.....

The sealed quotations are invited for Repairing , flooring and miscellaneous work at Oxygen store, KGMU. The details of quotation notice can be seen at website www.kgmu.edu and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 16/02/2024

Details of work as given below:-

S.NO	Particulars	Quantity	Unit	Rate
1	Dismantling cement concrete or brick or granolithic floor, including base concrete and including stacking of dismantled material as directed by the engineer in charge with in a distance of 60mtr.	67.09	Sqm	
2	Dismantling door, windows and clerestory windows (steel and wood) shutter including chawkhat architrave , holdfast etc complete and stacking within 50mtr lead	7	Nos	
3	Half brick masonry with common burnt clay brick class 150 in superstructure above plint level upto floor 5 th level. Cement mortar 1:3 (1 cement: 3 coarse sand)	10.64	Sqm	
4	Brick work with common burnt clay (non modular) bricks of class-150 in superstructure above plinth level up to floor 5 level in all stage and size in: Cement mortar 1:6 (1 cement : 4 coarse sand).	0.37	Cum	
5	Providing and laying in position plan cement concrete of specified grade : 1:6:12 (1 cement : 6 coarse sand, 12 graded brick aggregate 40mm.	0.87	Cum	
6	12mm cement plaster of mix 1:4 (1 cement : 4 coarse sand).	13.44	Sqm	
7	Applying coat of water thinnable cement primer of approved brand and manufacture on new plastered wall surface.	13.44	Sqm	
8	Steel reinforcement for RCC including, straightening, cutting bending, placing in position and binding all complete upto plinth level. Mild steel and medium tensile steel bar.	80	Kg	
9	Providing and laying in cement concrete of specified grade : 1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20mm.	1.08	Cum	
10	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand :4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc complete. 40mm thick with 20mm nominal size stone aggregate.	56.24	Sqm	
11	S/L of 1800mmx900mmx12mm thick chequered rubber matting of tested quality.	3	Nos	
12	Providing carpenter with helper for repairing of old door/window.	3	Nos	
13	Semi skilled labour for plant cutting and for miscellaneous civil work.	5	Nos	



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2253171 Email eng.civil@kgmcindia.edu

पत्रांक: -----


		दिनांक:	
14	Sweeper per pair with tools.	3	Nos
15	Providing cartage for disposal of malwa, refuse material from site as per direction of engineer in charge.	5.42	Cum

Terms & Conditions

- 1.G.S.T and labour cess shall be paid or deducted as per rules applicable.
- 2.The work will be completed within given time.
- 3.Quantity can be increase or decrease as per requirements.
- 4.Conditional quotations are liable to be rejected.
- 5.The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully


(Shailendra Singh)
Executive Engineer


(Dinesh Kumar Raj)
Superintending Engineer

No. 2103/10 of DT.

Copy for information and necessary action to:-

- 1.Registrar, King George's Medical University U.P, Lucknow.
2. Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date 08/02/24 To 18/02/2024
3. Sri Anjani kumar, Assistant Engineer, Works deptt. K.G.M.U.U.P.Lucknow
4. Sri Prateek Dubey, Junior Engineer, Works deptt. K.G.M.U.U.P.Lucknow
5. Notice Board.

Yours faithfully


(Shailendra Singh)
Executive Engineer


(Dinesh Kumar Raj)
Superintending Engineer

