



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2253171 Email eng.civil@kgmcindia.edu

पत्रांक: -----

264/M10

QUOTATION NOTICE

दिनांक: 08/02/2024

To,

M/s.....

.....

The sealed quotations are invited P/F of Iron gate , painting work and miscellaneous civil work at Respiratory Medicine department, KGMU. The details of quotation notice can be seen at website www.kgmu.edu and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 10/02/2024

Details of work as given below:-

S.NO	Particulars	Quantity	Unit	Rate
1	Scraping old white or colour wash etc. including disposal of refuse material as directed by Engineer-in-charge.	147.69	Sqm	
2	Brick work with common burnt clay (non modular) bricks of class-150 in superstructure above plinth level up to floor 5 level in all stage and size in: Cement mortar 1:6 (1 cement : 4 coarse sand).	0.18	Cum	
3	Providing and fixing 1mm thick MS sheet door with frame of 40x40x6 mm angle iron and 3mm MS gusset plate at junctions and corner all necessary fittings complete including applying a primer coat of approved steel primer.	1.80	Sqm	
4	12mm cement plaster of mix 1:4 (1 cement : 4 coarse sand).	0.81	Sqm	
5	Providing and laying in cement concrete of specified grade : 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm).	0.06	Cum	
6	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand :4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc complete. 40mm thick with 20mm nominal size stone aggregate.	3.12	Sqm	
7	Applying coat of water thinnable cement primer of approved brand and manufacture on new plastered wall surface.	0.81	Sqm	
8	Providing and applying white cement based putty of average thickness 0.60 mm of approved brand and manufacture, over the old plastered wall surface to prepare the surface even and smooth complete.	169.64	Sqm	
9	Providing and applying white cement based putty of average thickness 1 mm of approved brand and manufacture, over the old plastered wall surface to prepare the surface even and smooth complete.	0.81	Sqm	
10	Oil bound distemper in two coat.	260.76	Sqm	
11	Finishing walls with premium acrylic smooth exterior paint with silicone additives of required shade old work (two or more coats applied @ 1.43 ltr/10 sqm) over existing cement paint surface (apex ultima , weather coat all guard).	108.47	Sqm	
12	Laying old cement concrete interlock paver block of any design/shape laid in required line , level , curvature ,colour and pattern over and including 50mm thick compacted bed of	19.20	Sqm	



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2253171 Email eng.civil@kgmcindia.edu

पत्रांक: -----

			दिनांक:	
	course sand, filling the joint with fine sand etc. all complete as per the direction of engineer-in-charge (old CC paver block shall be supplied by the department free of cost).			
13	Providing and laying of interlocking concrete block pavement having thickness 60mm.	3.24	Sqm	
14	Providing and laying in position plan cement concrete of specified grade : 1:6:12 (1 cement : 6 coarse sand, 12 graded brick aggregate 40mm).	1.22	Cum	
15	Providing of concentrated Acid for removal of solid disposal in C.I drainage lines with cost of material, labour, T&P complete in all respect.	10	Ltr	
16	P/F of stainless steel sink without drain board of size 610x510mm bowl depth 200mm complete in all respect.	1	Nos	
17	P/F of CPVC pipes of approved quality including cost of material, labour, T&P complete in all respect. 25mm dia	6.12	Rmt	
18	P/L Kajaria or equivalent wall tiles in size 300x600mm with water absorption less than 0.08% and conforming to IS: 15622 of approved make in all colours and sheds, laid on 20mm thick cement mortar in 1:3 cement coarse sand including grouting of joints with white cement and matching pigment etc. complete.	1.73	Sqm	
19	Providing carpenter with helper for repairing of old door/window.	2	Nos	
20	Sweeper per pair with tools.	10	Nos	
21	Semi skilled labour for unwanted plant cutting and for miscellaneous civil work.	6	Nos	

Terms & Conditions

- 1.G.S.T and labour cess shall be paid or deducted as per rules applicable.
- 2.The work will be completed within given time.
- 3.Quantity can be increase or decrease as per requirements.
- 4.Conditional quotations are liable to be rejected.
- 5.The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully


(Shailendra Singh)
Executive Engineer


(Dinesh Kumar Raj)
Superintending Engineer

No. 2104/MK0 / of DT.

Copy for information and necessary action to:-

- 1.Registrar, King George's Medical University U.P, Lucknow.
2. Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date 08/02/24 To 18/02/2024
3. Sri Anjani kumar, Assistant Engineer, Works deptt. K.G.M.U.U.P.Lucknow



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2253171 Email eng.civil@kgmcindia.edu

पत्रांक: -----

4. Sri Prateek Dubey, Junior Engineer, Works deptt. K.G.M.U.U.P.Lucknow
5. Notice Board.

दिनांक:

Yours faithfully

(Shailendra Singh)
Executive Engineer

(Dinesh Kumar Raj)
Superintending Engineer