



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003 निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 ई-मेल : eng.civil@kgmcindia.edu

पत्रांक: _____

2031/M10

QUOTATION NOTICE

दिनांक: _____
29/1/2024

To,

M/s.....
.....
.....

The sealed quotations are invited for Providing and fixing aluminium partition for blood collection counter at ground floor of CVTS building KGMU. The details of quotation notice can be seen at website www.kgmu.org and on the Notice board of the office of undersigned. Registered contractors of kgmu may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 05/02/2024

Details of work as given below:-

S.No.	Particulars	Quantity	Unit	Rate
1.	P/F anodised aluminium work for doors, windows and ventilators with extruded built up standard tabular sections/ appropriate Z section and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/neoprene gasket etc.	37.80	Kg.	
2.	P/F anodised aluminium work for partitions with extruded built up standard tabular sections/ appropriate Z section and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/neoprene gasket etc.	79.44	Kg.	
3.	P/F float glass panes of 5mm thick in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber /neoprene gasket etc. complete as per directions of E/I.	5.47	Sqm.	
4.	P/F 4mm thick ACP sheet in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber/neoprene gasket etc. complete as per the architectural drawings and the directions of E/I.	6.48	Sqm.	
5.	P/F of S.S hinges 100mm long with stainless steel screws etc. complete.	12	Nos.	
6.	P/F aluminium handle 100mm long of approved quality complete.	06	Nos.	
7.	P/f Aluminium sliding door bolt with 16mm dia and 200mm long.	02	Nos.	
8.	P/f Aluminium tower bolt with 10mm dia and 250mm long.	03	Nos.	
9.	P/F aluminium door stopper of approved quality complete.	03	Nos.	
10.	S/F of appd quality door closer ISI marked. Godrej or equivalent.	02	Nos.	
11.	Providing labour for cleaning of site and collecting malwa.	06	Nos.	
12.	Cartage for disposal of malwa up to 10km away from site.	5.40	Cum.	

Terms & Conditions

1. G.S.T and labour cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.

Roy
JET



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003
निर्माण विभाग


फोन (कुलसचिव कार्यालय) : 0522-2257540 ई-मेल : eng.civil@kgmcindia.edu


पत्रांक: -----

5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

दिनांक:

Yours faithfully



(Suresh Kumar)
Executive Engineer



(Dinesh Kumar Raj)
Superintending Engineer

No. 2031/Mre of DT.

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date 29/07/2024 To 5/02/2024
3. Sri T.C. Yadav, Assistant Engineer, Works deptt. K.G.M.U. U.P. Lucknow
4. Sri Poshit roy, Junior Engineer, Works deptt. K.G.M.U. U.P. Lucknow
5. Notice Board.


(Suresh Kumar)
Executive Engineer


(Dinesh Kumar Raj)
Superintending Engineer


P. Roy
JE