



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu.

पत्रांक: -----

1998/110

QUOTATION NOTICE

दिनांक:.....

01/11/2023

To,
M/s.....
.....
.....

The sealed quotations are invited for repairing and painting of room nos. 28,30,31,50 and other misc. work at first floor in Old V.L. Hostel kgmu from the registered contractor of KGMU. The detail of quotation notice can be seen at website www.kgmcindia.edu and on the Notice board of the office of undersigned Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 07/11/2023

Details of the work as given below-

Sl.No.	Particulars	Qty.	Unit	Rate
1	Dismantling existing old plaster including disposal of refuse as directed by engineer incharge.	74.56	Sqm.	
2	18mm cement plaster in two coats under layer 12mm thick cement plaster 1:5(1 cement: 5 course sand) and a top layer 6mm thick cement plaster 1:3(1cement: 3course sand) finished rough with sponge.	30.62	Sqm.	
3	P/L 12mm cement plaster in 1:6 on wall with cement and coarse sand including supply of all material labour and T&p etc. for proper completion of the work.	43.94	Sqm.	
4	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface.	74.56	Sqm.	
5	Providing and laying white cement based putty of average thickness 1mm of approved brand on new plastered surface to prepare the surface even and smooth complete.	74.56	Sqm.	
6	Scraping old white or colour wash etc. including disposal of refuse material as directed by Engineer-in-charge.	242.35	Sqm.	
7	Providing and laying cement based white putty of average thickness 0.60mm of approved brand and manufacture, over the old painted wall surface to prepare the surface even and smooth complete.	242.35	Sqm.	
8	Distempering with oil bound distemper two coat of approved brand old Surface to give an even shade including all material, labour T&P etc. complete.	316.91	Sqm.	
9	Painting two coats with Supirior synthetic enamel paint in old Surface including supply of labour material t&p etc. complete.	68.09	Sqm.	
10	Providing welding machine with welder without rod and power for repairing of old M.S grill.	01	No.	
11	Providing labour for cleaning of site and collecting malwa.	02	Nos.	
12	Cartage for disposal of malwa up to 10km away from site.	2.71.	Cum.	

Samadh
J.E



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu.

पत्रांक: -----

Terms & Conditions.

दिनांक:.....

1. G.S.T & Labour Cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully

(Shailendra Singh)
Executive Engineer

(Dinesh Kumar Raj)
Superintending Engineer

Shailendra Singh
S.E

Dinesh Kumar Raj
A.E

No. 1496/2020 of DT.

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date 01/11/2020 To 07/11/2020
3. Sri Shailendra Singh, Executive Engineer, Works deptt. K.G.M.U.U.P.Lucknow
4. Sri Anjani Kumar, Assistant Engineer, Works deptt. K.G.M.U.U.P.Lucknow
5. Sri Karuna Nidhi, Junior Engineer, Works deptt. K.G.M.U.U.P.Lucknow
6. Notice Board.

(Shailendra Singh)
Executive Engineer

(Dinesh Kumar Raj)
Superintending Engineer

Shailendra Singh
S.E

Dinesh Kumar Raj
A.E