



# किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

## निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2253171 फैक्स : 0522&225753 वेबसाइट : www.kgmu.org.

पत्रांक: 2289/M10

दिनांक: 16/03/2024

### QUOTATION NOTICE

To,  
M/s.....  
.....  
.....

The sealed quotations are invited for repair and fixing of water supply pipeline and other misc work in ground floor toilet at old VL hostel from the registered contractor of KGMU. The detail of quotation notice can be seen at website [www.kgmcindia.edu](http://www.kgmcindia.edu) and on the Notice board of the office of undersigned Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 22/03/2024

Details of the work as given below-

Sl.No.	Particulars	Qty.	Unit	Rate
1.	Dismantling existing old plaster including disposal of refuse as directed by engineer incharge.	16.80	Sqm.	
2.	Dismantling old damaged floors, including stacking of dismantling material as per direction by the E/I.	3.90	Sqm.	
3.	P/F CPVC pipes 25mm dia., having thermal stability or hot & cold water supply, including all CPVC plain and brass threaded fittings, l/c fixing the pipe with clamps at 1m spacing. This includes jointing of pipes and fitting with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of E/I complete.	15.70	Rmt.	
4.	P/F CPVC pipes 20mm dia., having thermal stability or hot & cold water supply, including all CPVC plain and brass threaded fittings, l/c fixing the pipe with clamps at 1m spacing. This includes jointing of pipes and fitting with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of E/I complete.	7.20	Rmt.	
5.	P/L 12mm cement plaster in 1:6 on wall with cement and coarse sand including supply of all material labour and T&p etc. for proper completion of the work.	0.72	Sqm.	
6.	P/L vitrified floor tiles in 600x600mm (thickness to be specified by the manufacture ) with water absorption less than 0.08% and conforming to IS: 15622 of approved make in all colours and shades , laid on 20mm thick cement mortar in 1:4 cement coarse sand including grouting of joints with white cement and matching pigment etc. complete.	3.90	Sqm.	
7.	P/L wall tiles 200x300mm with water absorption less then 0.08% and conforming to IS: 15622 of approved make in all colours and shades , laid on 12mm thick cement mortar in 1:3 cement coarse sand including grouting of jointes with white cement and matching pigment.	16.08	Sqm.	

*(Signature)*



# किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

## निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2253171 फैक्स : 0522&225753 वेबसाइट : www.kgmu.org.

पत्रांक: -----


दिनांक:.....


8.	Grouting the jointes of flooring tiles size 600x600 having jointes of 3mm width, using epoxy grout mix of 0.70 kg of organic coated filler of desired of shade including grouting filling and finishing complete.	36.42	Sqm.	
9.	S/F of HCI pipe with socket including fitting 100mm dia. approved quality.	6.10	Rmt.	
10.	S/F C.I Nahani trap 100mm dia .	4	Nos.	
11.	S/F C.I P trap 100mm dia approved quality.	4	No.	
12.	S/F C.I plain tee 100mm dia.	3	Nos.	
13.	P/F of white vitreous china Orissa Pattan W.C. Pan of 580x440 mm dia with integral type foot rests.	3	Nos.	
14.	Providing and fixing white vitreous china pedestal type(European type/wash down type) water closet pan.	1	No.	
15.	S/F 10 Lit PVC low down cistern for appd. Quality in completed.	4	Nos.	
16.	P/F of Brass Socket 25 x 25mm heavy quality	1	No.	
17.	S/F of C.P floor jaali heavy quality 100mm dia.	4	Nos.	
18.	Providing plumber with helper for repairing removing and refixing old fittings.	1	No.	
19.	Providing labour (unskilled) for cleaning of site and collecting malwa.	1	No	
20.	Cartage for disposal of malwa upto 10km away from the site.	2.71	Cum.	

### Terms & Conditions.

1. G.S.T & Labour Cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully


  
Executive Engineer


  
(Dinesh Kumar Raj)  
Superintending Engineer

No. 2289/M/10 of DT.

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date. 11/03/24 To 22/03/24
3. Sri Anjani Kumar, Assistant Engineer, Works deptt. K.G.M.U.U.P. Lucknow
4. Sri Karuna Nidhi, Junior Engineer, Works deptt. K.G.M.U.U.P. Lucknow
5. Notice Board.

  
Executive Engineer

  
(Dinesh Kumar Raj)  
Superintending Engineer