



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 ई-मेल : eng.civil@kgmcindia.edu

पत्रांक: -----

1945/M10

QUOTATION NOTICE

दिनांक:.....

11/01/2024

To,

M/s.....

.....

The sealed quotations are invited for Repairing of drain near lawn including other misc. work at ABV scientific convention center KGMU. The details of quotation notice can be seen at website www.kgmu.org and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 18/01/2024....

Details of work as given below:-

S.No.	Particulars	Quantity	Unit	Rate
1.	Taking out existing CC interlocking paver blocks from footpath/ central verge, including removal of rubbish etc., disposal of unserviceable material to the dumping ground, for which payment shall be made separately and stacking of serviceable material within 50 metre lead as per direction of Engineer-in-Charge.	9.80	Sqm.	
2.	Earth work in excavation in trenches for foundations in ordinary soil including lift upto 1.5 m. lead upto 50m and dressing of sides and rammings of bottom.	3.17	Cum.	
3.	P/L PCC 1:5:8 cement, fine sand & 40mm stone ballast.	4.55	Cum.	
4.	P/L cement concrete in 1:2:4 cement, coarse sand 20mm stone grit.	2.51	Cum.	
5.	P/L 12mm cement plaster in 1:3 (1 Cement :3Coarse sand) finished with a floating coat of neat cement.	1.62	Sqm.	
6.	Laying old cement concrete interlocking paver blocks of any design/ shape laid in required line, level, curvature, colour and pattern over and including 50 mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineerin-charge.	9.80	Sqm.	
7.	Making connection of drain or sewer line with existing manhole including breaking into and making good the walls, floors with cement concrete 1:2:4 complete	02	Nos.	
8.	P/F PVC pipe 150mm dia. 6kg pressure make of approved quality complete.	3.50	Rmt.	
9.	P/F PVC pipe 300mm dia. 6kg pressure make of approved quality complete.	3.00	Rmt.	
10.	Providing welder with welding machine for repairing and refixing.	03	Nos.	
11.	Providing labour for cleaning of site and shifting of material.	06	Nos.	

Terms & Conditions

1. G.S.T and labour cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.

Ray
JE



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003
निर्माण विभाग


फोन (कुलसचिव कार्यालय) : 0522-2257540 ई-मेल : eng.civil@kgmcindia.edu

पत्रांक: -----

दिनांक:.....

4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully



(Suresh Kumar)
Executive Engineer


(Dinesh Kumar Raj)
Superintending Engineer

No. 1945/MMO / of DT.

Copy for information and necessary action to:-

1. Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date 11/01/2024 To 18/01/2024
2. Sri T.C. Yadav, Assistant Engineer, Works deptt. K.G.M.U. U.P. Lucknow
3. Sri Poshit roy, Junior Engineer, Works deptt. K.G.M.U. U.P. Lucknow
4. Notice Board.


(Suresh Kumar)
Executive Engineer


(Dinesh Kumar Raj)
Superintending Engineer


JE