



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

फोन (कुलसचिव कार्यालय) : 0522-2253171 ई-मेल: eng.civil@kgmcindia.edu

पत्रांक: 2303/एम-10/2024

दिनांक: 19/03/2024

QUOTATION NOTICE

To,

M/s.....

The sealed quotations are invited Repairing of drainage and side apron of underground water tank at backside of new OPD Building at kgmu from the registered contractor of KGMU. The details of quotation notice can be seen at website www.kgmcindia.edu and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 26/03/2024

Details of the work as given below-

S.No	Particular	Qty	Unit	Rates
1.	Dismantling cement concrete or granolithic floors, including stacking of dismantling materials as per direction by the E/I.	43.17	Sqm	
2.	Dismantling of Existing old plaster.	6.24	Sqm	
3.	Cement plaster 1:3 (1 cement :3 coarse sand) finished with a floating coat of neat cement 12mm cement plaster.	37.2	Sqm	
4.	M-150 class 120mm thick brick work in 1:4 cement & coarse sand in super structure including supply of all materials, labours and T&P etc for proper completion of the work.	1.89	Sqm	
5.	M-150 class 230mm thick brick work in 1:4 cement & coarse sand in super structure including supply of all materials, labours and T&P etc for proper completion of the work.	0.19	Cum	
6.	C.C. work in 1:2:4 cement C-Sand stone aggregate.	2.91	Cum	
7.	P/L P.C.C. 1:5:10 cement, fine sand and 40mm brick ballast in foundation.	4.01	Cum	
8.	Reinforced cement concrete work in chamber cover 1:1.5:3 (1 cement : 1.5 coarse sand(zone-3) : 3 graded stone aggregate 20mm nominal size).	0.24	Cum	
9.	Mild Steel work 10/12mm dia as for reinforcement.	30.26	Kg.	
10.	Fabrication of M.S. frame with M.S. angles.	72.00	Kg	
11.	Providing labour for miscellaneous work.	10	Nos.	
12.	Providing Sweeper for cleaning of old seewage.	3	Per day	
13.	Providing welding plant with operator without rod & power for repairing.	2	Per Day	
14.	Cartage for disposal of malwa upto 10 km away from the site.	9.15	Cum	

Terms & Conditions

1. G.S.T and labourcess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotation are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

(Anupam Mishra)
Executive Engineer

Yours Faithfully
(Dinesh Kumar Raj)
Superintending Engineer

No...../

Date.....



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

फोन (कुलसचिव कार्यालय) : 0522-2253171 ई-मेल: eng.civil@kgmcindia.edu


पत्रांक: 2303 / एम-10 / 2024

दिनांक:

Copy for Information and necessary action to:

1. Registrar, K.G.M.U. U.P. Lucknow
2. Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date. 19/03/24 To 28/03/24
3. Sri Yashvant Singh, Assistant Engineer, Works deptt, K.G.M.U, U.P. Lucknow
4. Sri Sumit Kanaujia, Junior Engineer, Works deptt. K.G.M.U, U.P. Lucknow
5. Notice Board


(Anupam Mishra)
Executive Engineer


(Dinesh Kumar Raj)
Superintending Engineer

