



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 वेबसाइट : www.kgmu.org

पत्रांक: -----

1794/MO/

QUOTATION NOTICE

दिनांक:

21/12/2023

To,

M/s.....

.....

The sealed quotations are invited for repairing of old damaged floor tiles, wall tiles and sanitary fittings in toilet block including repairing painting and other misc. work at biochemistry department the detail of quotation notice can be seen at website www.kgmu.org and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated

28/12/2023

Details of the work as given below-

Sl.No.	Particulars	Qty.	Unit	Rate
1.	Dismantling cement concrete or granolithic floors, including stacking of dismantling material as per direction by the E/I.	6.30	Sqm	
2.	Dismantling existing old plaster including disposal of refuse as directed by engineer incharge.	4.38	Sqm	
3.	Making the opening in brick masonry including dismantling in floor or wall by cuttings masonry and making good the damage to walls flooring and jambs complete to match existing surface I/C disposal of mulba rubbish to the nearest municipal dumping ground all complete	5.25	Sqm	
4.	P/L cement concrete in 1:2:4 cement, coarse sand 20mm stone grit.	0.25	Cum	
5.	P/L floor tiles in size 300x300mm with water absorption less than 0.08% and conforming to IS: 15622 of approved make in all colours and sheds laid on 1:4 cement coarse sand including grouting of joints with white cement and matching pigment etc. complete.	6.30	Sqm	
6.	P/L wall tiles 300x600mm with water absorption less than 0.08% and conforming to IS: 15622 of approved make in all colours and sheds, laid on 12mm thick cement mortar in 1:3 cement coarse sand including grouting of joints with white cement and matching pigment	4.38	Sqm	
7.	P/L 12mm cement plaster in 1:6 on wall with cement and coarse sand including supply of all material labour and T&p etc. for proper completion of the work.	1.25	Sqm	
8.	S/f anodized aluminum grill all including stainless steel wire gauze for including all labour material t&p etc.up to proper complete of work	1.04	Sqm	
9.	P/F G.I metal tile clip in plain beveled edge global white colour tile size 600x600mm and 0.5mm thick.	3.60	Sqm	
10.	P/F inter locking metal false ceiling grid of hot dipped galvanized steel section consisting of main tee runner with suitable spaced joint "T" gates required length and of size 24x38mm made from 0.30mm thick sheet, spaced and 1200mm center to center and cross tee of size 24x25mm made of 0.30mm thick sheet, 1200mm long spaced between main "T" at 600mm center to center from to grid.	22.02	Sqm	
11.	Scraping old white or colour wash etc.including disposal of refuse material as directed by Engineer-in-charge.	48.93	Sqm	
12.	Providing and laying cement based white putty of average thickness 0.60mm of approved brand and manufacture, over the old painted wall surface to prepare the surface even and smooth complete.	48.93	Sqm	
13.	Distemping with oil bound distemper two coat of approved brand on old Surface to give an even shade including all material, labour T&P etc. complete.	76.45	Sqm	
14.	Application of two coats apex Ultima paint on outer surface including supply of all materials, labours and T&P etc. for proper completion of the work.	25.75	Sqm	

TRay
JE



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 वेबसाइट : www.kgmu.org

पत्रांक: -----


दिनांक:

15.	Painting two coats with Superior synthetic enamel paint in new Surface with one coat primer including supply of labour material t&p etc. complete.	13.74	Sqm	
16.	White glazed earthen ware (European type) W.C pan 505 mm dia with seat cover of jaguar ESSCO, cera hindware.	01	No.	
17.	S/F 10 Lit PVC low down cistern for appd. Quality in completed.	01	No.	
18.	S/F wash basin white glazed 22"x16" complete with pillar cock, bracket, waste jali, waste pipe, PVC connection etc.	01	No.	
19.	S/F of C.P brass short body bib cock 15mm dia. Make of appd.	02	Nos	
20.	S/F PVC connection 600mm long Prayag make.	02	Nos	
21.	S/F C.P extention piece 15x50mm long	03	Nos	
22.	S/F C.P waste coupling full threaded for basin	01	No.	
23.	S/F C.P Angle valve 15mm dia. make of appd quality.	03	Nos	
24.	S/F C.P pillar cock 15mm dia. make of appd quality.	01	No.	
25.	S/F C.P floor jaali 110mm dia.	03	Nos	
26.	Caratge for disposal of malwa from site.	2.26	Cum	
27.	Providing carpanter with helper for repair of old doors and windows.	01	No.	
28.	Fabrication of MS angle for window with welding complete	37.07	Kg	
29.	Providing welding machine with welder for Repair of old M.S gate.	02	Nos.	
30.	Providing labour for cleaning of site and collecting malwa	04	Nos	

Terms & Conditions.

1. G.S.T & Labour Cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.


Yours faithfully


(Suresh Kumar) (Dinesh Kumar Raj)
Executive Engineer Superintendent Engineer

No. 1774/MC of DT.

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date 21/12/2022 To 28/12/2023
3. Sri T.C Yadav, Assistant Engineer, Works deptt. K.G.M.U.U.P.Lucknow
4. Sri Poshit Roy, Junior Engineer, Works deptt. K.G.M.U.U.P.Lucknow
5. Notice Board.


(Suresh Kumar) (Dinesh Kumar Raj)
Executive Engineer Superintendent Engineer


JE