



# किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

## निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 ई-मेल : eng.civil@kgmcindia.edu

पत्रांक: -----

1619/M/10

### QUOTATION NOTICE

दिनांक:.....

29/11/23

To,

M/s.....

.....

The sealed quotations are invited for Repairing, painting and other misc. work of outer front portion at pathology department KGMU. The details of quotation notice can be seen at website [www.kgmu.org](http://www.kgmu.org) and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 29/11/23.

Details of work as given below:-

S.No.	Particulars	Quantity	Unit	Rate
1.	Dismantling existing old plaster including disposal of dismantled as directed by engineer incharge.	2.44	Sqm.	
2.	P/L PCC 1:5:8 cement, fine sand & 40mm stone ballast.	0.36	Cum.	
3.	Scraping old white or colour wash etc.including disposal of refuse material as directed by Engineer-in-charge.	220.78	Sqm.	
4.	P/L 12mm cement plaster in 1:6 on wall with cement and coarse sand including supply of all material labour and T&p etc. for proper completion of the work.	2.44	Sqm.	
5.	P/L cement concrete in 1:2:4 cement ,coarse sand 20mm stone grit.	0.60	Cum.	
6.	Providing and laying white cement based putty of average thickness 1mm of approved brand on new plastered surface to prepare the surface even and smooth complete.	2.44	Sqm.	
7.	Providing and laying cement based white putty of average thickness 0.60mm of approved brand and manufacture, over the old painted wall surface to prepare the surface even and smooth complete.	220.78	Sqm.	
8.	Application of two coats apex Ultima paint on outer surface including supply of all materials, labours and T&P etc. for proper completion of the work.	220.78	Sqm.	
9.	Painting two coats with Superior synthetic enamel paint in old Surface including supply of labour material t&p etc. complete.	31.96	Sqm.	
10.	Providing & fixing glass panes 5 mm thick with putty and glazing clips in steel doors, windows, clerestory windows, all complete.	1.20	Sqm.	
11.	P/F CPVC pipes 25mm dia., having thermal stability or hot & cold water supply, including all CPVC plain and brass threaded fittings, l/c fixing the pipe with clamps at 1m spacing. This includes jointing of pipes and fitting with one step CPVC solvent cement including testing of joints complete as per direction of E/I complete.	3.00	Rmt.	
12.	P/L of appd. Quality 60mm thick unipaver rubber molding interlocking tiles notless than 30MPa including leveling and dressing of surface to required level and slope, filling joints local sand and also including the cost of all material, labour T&p complete.	4.50	Sqm.	
13.	P/F brass ball valve 15mm dia. Of approved brand complete.	01	No.	
14.	P/F brass ball valve 25mm dia. Of approved brand complete.	01	No.	

IRoy  
JE



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003  
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 ई-मेल : eng.civil@kgmcindia.edu

पत्रांक: .....


दिनांक: .....

15.	Providing labour for cleaning of site and collecting malwa.	06	Nos.	
-----	---	----	------	--

**Terms & Conditions**

1. G.S.T and labour cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully

  
(Suresh Kumar)  
Executive Engineer

  
(Dinesh Kumar Raj)  
Superintending Engineer

  
JE

No...../ of DT.

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date 21/11/2023 To 29/11/2023
3. Sri T.C. Yadav, Assistant Engineer, Works deptt. K.G.M.U. U.P. Lucknow
4. Sri Poshit roy, Junior Engineer, Works deptt. K.G.M.U. U.P. Lucknow
5. Notice Board.

  
(Suresh Kumar)  
Executive Engineer

  
(Dinesh Kumar Raj)  
Superintending Engineer

  
JE