



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2253171 फैक्स : 0522&225753 वेबसाइट : www.kgmu.org.

पत्रांक:

1638/M-10/2023

दिनांक: 28/11/23

QUOTATION NOTICE

To,

M/s.....

.....

The sealed quotations are invited for p/f of M.S Gate at back side of hostel, repairing and painting of first floor of bathroom including other misc. work at DK and chhatra chatrawas hostel(near Old VL Hostel) from the registered contractor of KGMU. The detail of quotation notice can be seen at website www.kgmu.org and on the Notice board of the office of undersigned Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated .. 04/12/2023 ..

Details of the work as given below-

Sl.No.	Particulars	Qty.	Unit	Rate
1.	Earth work in excavation in trenches for foundations in ordinary soil including lift up to 1.5m. Lead up to 50m and dressing of sides and ramming of bottom.	0.95	Cum	
2.	Dismantling existing old plaster including disposal of refuse as directed by engineer in charge.	23.36	Sqm.	
3.	Dismantling old damaged floors tiles including stacking of dismantling material as per direction by the E/I.	2.25	Sqm.	
4.	18mm cement plaster in two coats under layer 12mm thick cement plaster 1:5(1 cement : 5 course sand) and a top layer 6mm thick cement plaster 1:3(1cement : 3course sand)finished rough with sponge.	23.36	Sqm.	
5.	P/L PCC 1:5:8 cement, fine sand& 40mm stone ballast.	0.19	Cum	
6.	M-150 Class 230mm thick brick work in 1:4 cement coarse sand in foundation including supply of all materials, labors and T&P etc. for proper completion of the work.	0.45	Cum.	
7.	M-150 class 230mm thick brick work in 1:4 cement & coarse sand in super structure including supply of all materials, labors and T&P etc.for proper completion of the work.	1.76	Cum.	
8.	P/L 12mm cement plaster in 1:6 on wall with cement and coarse sand including supply of all material labor and T&p etc. for proper completion of the work.	19.46	Sqm.	
9.	P/L RCC work in lintel/platform 1:1.5:3 cement, coarse sand and stone aggregate.	0.04	Cum.	
10.	Mild steel work for reinforcement in plain concrete work including cutting bending and binding and also including binding wire.	8.12	Kg.	
11.	P/L floor tiles in size 300x300mm with water absorption less than 0.08% and conforming to IS: 15622 of approved make in all colours and sheds , laid on 1:4 cement coarse sand including grouting of joints with white cement and matching pigment etc. complete.	2.25	Sqm.	
12.	Fabrication of M.S structure with M.S angle with welding complete.	38.10	Kg.	

Tanvirul
J.E



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2253171 फैक्स : 0522&225753 बेवसाइट : www.kgmu.org.

पत्रांक: -----

दिनांक:.....

13	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface.	42.82	Sqm.	
14.	Providing and laying white cement based putty of average thickness 1mm of approved brand on new plastered surface to prepare the surface even and smooth complete.	42.82	Sqm.	
15.	Scraping old white or colour wash etc. including disposal of refuse material as directed by Engineer-in-charge.	87.74	Sqm.	
16.	Providing and laying cement based white putty of average thickness 0.60mm of approved brand and manufacture, over the old painted wall surface to prepare the surface even and smooth complete.	87.74	Sqm.	
17.	Distempering with oil bound distemper two coat of approved brand old Surface to give an even shade including all material , labour T&P etc. complete.	111.10	Sqm.	
18.	Application of two coats apex Ultima paint on outer surface including supply of all materials, labours and T&P etc. for proper completion of the work	19.46	Sqm.	
19.	Painting 2coat with supirior synthetic enaniel paint with priming coat on new surface upto 10 cm width or grith.	4.41	Sqm.	
20.	Painting two coats with Supirior synthetic enamel paint in old Surface including supply of labour material t&p etc. complete.	5.19	Sqm.	
21.	Fencing with G.I. barbed wire with angle iron post placed at required distance embedded in cement concrete blocks, every 15th post, last but one end post and corner post shall be strutted on both sides and provided with horizontal lines and two diagonals interwoven with horizontal wires, of barbed wire weighing 9.38 kg per 100 m (minimum), between the two posts fitted and fixed with G.I. staples, turn buckles etc. complete. With G.I. barbed wire.	150.00	Rmt.	
22.	S/F G.I pipe 20mm dia B class complete.	6.10	Nos.	
23.	S/F G.I elbow 20mm dia B class complete.	04	Nos.	
24	S/F ball cock 25mm dia of approved quality	03	Nos.	
25	S/F brass ball valve 25mm dia. Of approved quality, high or low pressure. NMV make	03	Nos.	
26	S/F G.I elbow 20mm dia B class complete.	05	Nos.	
27	S/F G.I elbow 25mm dia B class complete.	04	Nos.	
28	Providing welding machine with welder without rod and power for repairing of old M.S grill.	02	Nos.	
29	Providing Carpenter with helper for repairing of old door/window.	02	Nos.	
30.	Providing Plumber with helper for repairing of old fitting.	02	Nos..	

Handwritten signature
J.B



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003
निर्माण विभाग

फोन (कूलसचिव कार्यालय) : 0522-2253171 फैक्स : 0522&225753 बेवसाइट : www.kgmu.org.

पत्रांक: -----

दिनांक:.....


31	Providing labour for cleaning of site and collecting malwa.	04	Nos.	
32	Cartage for disposal of malwa up to 10km away from site.	2.71	Cum.	


Terms & Conditions.

1. G.S.T & Labour Cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully


(Shailendra Singh)
Executive Engineer


(Dinesh Kumar Raj)
Superintending Engineer


J.B.


A.E.


No...../ of DT.

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date... 22/11/2023 To... 04/12/2023
3. Sri Shailendra Singh, Executive Engineer, Works deptt. K.G.M.U.U.P.Lucknow
4. Sri Anjani Kumar, Assistant Engineer, Works deptt. K.G.M.U.U.P.Lucknow
5. Sri Karuna Nidhi, Junior Engineer, Works deptt. K.G.M.U.U.P.Lucknow
6. Notice Board.


(Shailendra Singh)
Executive Engineer


(Dinesh Kumar Raj)
Superintending Engineer


J.B.


A.E.