

**WORKS DEPARTMENT, KING GEORGE'S MEDICAL
UNIVERSITY U.P, LUCKNOW.**

No. 3438 / M-10

dt. 18/12/17

Quotation Notice


Sub:- Providing and laying floor tiles on ramp and other misc. work at Trauma center KGMU.

Please quote your rates for the above work as per specifications given below. The sealed quotations should reach to undersigned duly marked on the envelope the number and date of this notice latest by 3.30P.m on dated 27/12/17

Sl.No	Particular	Qty	Unit.	Rates
1	Dismantling of old and unserviceable tiles including stacking of dismantled material.	13.50	Sqm	
2	P/L of Pavit's Granit antiskid floor tiles 300x300mm over 20mm thick cement mortar in 1:4 cement and coarse sand.	13.50	Sqm	
3	P/L of m.s flat 25x5mm on ramp including chase cutting and its repair complete.	28.56	Rmt.	
4	Application of two coats of Apex Ultima paint on old surface.	8.75	Sqm.	
5	Painting two coats synthetic enamel paint on old surface.	58.15	Sqm.	
6	Labour charges for repair of old collapsible gate at entrance in trauma center including replace of damage rail and m.s flat.	1	Job	
7	S/f of 4mm thick glass panes, with putty and nails wherever necessary including racking out the old putty.	10.10	Sqm.	
8	S/f of m.s sheet cover size 1.07x1.07mt. with m.s angle 35x35x5mm.	1	Job.	
9	S/f of m.s sheet cover size 1.25x1.37mt. with m.s angle 35x35x5mm.	1	Job.	
10	S/f of precast cement concrete cover 600x600mm on chamber with m.s angle frame	1	Np.	

Terms & condition

- 1- The quotation should be accepted by Registered Contractor of KGMU.
- 2- The rates should be quoted exclusive G.S.T.
- 3- The work will completed within one week from the date of order.
- 4- The quotation should be reached by Registered post upto date mentioned in quotation.


(Ram Velas Verma)
Executive Engineer

3439-44/M-10