

**WORKS DEPARTMENT, KING GEORGE'S MEDICAL UNIVERSITY  
U.P, LUCKNOW**

No. .... 4301 / M/10

Quotation Notice

of dt. 25/09/18

Sub:- Misc civil Sainitary for Resident Room & other work in New Building Corner side at Respiratory Medicine, K.G.M.U.

Dear sir,

Please quote your rates for the above work as per specifications given below. The sealed quotations should reach to undersigned duly marked on the envelope the number and date of this notice latest by 3:30 P.m on dated.....

Sl.No	Particular	Quantity	Unit	Rates
1	Scraping of colour white wash old surface.	135.06	Sqm	
2	P/L of Birla white putty for making good smooth surface.	135.06	Sqm	
3	Oil bound distemper in two coat.	135.06	Sqm	
4	Application of two coats Apex. Altima paint of Approved Brand on old Surface Given an even Shade including supply of all material, labour T&P as required for proper completion of work	378.78	Sqm	
5	Enamel painting in two coat	30.12	Sqm.	
6	Alluminium Door/Partition Repair Labour charge complete etc.	12.37	Sqm	
7	S/F of anodized alluminium grill all including stainless steel wire gauze for window including all labour material T & P etc. up to proper complete of work.	0.58	Sqm	
8	Difference of Nova Pan board in place of plain glass.	2.65	Sqm	
9	Providing and laying Vitrified tiles in floor with different sized(thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade laid with cement based high ploymer modified quick set tile adhesive(water based) conforming to IS:15477, in average 6mm. thickness, including grouting of joints (Payment for grouting of joints to be made separately) (Size of tile 600x600mm)	9.14	Sqm	
10	P/L Kajaria or equivalent wall tiles 300x600mm. with water absorption less than 0.08% and conforming to IS:15622 of approved make in all colours and sheds, lied on 20mm. thick cement mortar in 1:4 cement and coarse send including grouting of joints with white cement matching pigment.	4.86	Sqm	
11	S/F of G.I. pipe 15mm dia with fitting complete.	6.10	Rmt	
12	S/F of C.P. floor jali 100mm dia.	03	No	
13	Commod Sheat with cover (Cera Make)	01	Nos	
14	S/F wash basin 550x400mm with piller cock bracket, waste pipe waste jali, PVC connection etc, complete.	01	No	
15	S/F PVC angle valve 15mm dia	04	No	
16	S/F Urinal West Pipe	01	No	
17	S/F PVC short body bib cock 15mm dia.	01	No	
18	Hand shower	01	No	
19	S/F of C.I. Plain Band 100mm. dia	03	No	
20	S/F of C.I. Door Band 100mm. dia	03	No	
21	S/F of C.I. Plain T-100mm. dia	01	No	
22	S/F of C.I. Socket 100mm. dia	02	No	
23	S/F of Iron Clamp 100mm. dia	04	No	
24	S/F of Nahani Trap 100mm. dia	02	No	
25	S/F of C.I. P Trap 100mm. dia	01	No	

/F of Raj Shree P.V.C. door with chaukhet.

1.48

Sqm

Condition

The quotation should be accepted by Registered Contractor of KGMU.

The rates should be quoted excluding G.S.T.

The work will be completed within one week from the date of order.

4. The quotation should be reached by Registered post upto date mentioned in quotation.

Yours Faithfully

(Ram Velas Verma)  
Executive Engineer

*Ram Velas Verma*

No.

4302-07/M-10

Date 25/09/18

Copy for Information and necessary action to:

1. Registrar, K.G.M.U, U.P. Lucknow
2. Finance Officer, K.G.M.U, U.P. Lucknow
3. Head of Deptt. Respiratory Medicine, K.G.M.U, U.P. Lucknow
4. Dr. Sandeep Bhattacharya, Website Administration Finance & Contact, P.H.I Bhawan, KGMU for Uploading the quotation Notice in KGMU.
5. Assistant Engineer, Works deptt. K.G.M.U, U.P. Lucknow
6. Junior Engineer, Works deptt. K.G.M.U, U.P. Lucknow
7. Notice Board.

(Ram Velas Verma)  
Executive Engineer

*Ram Velas Verma*