



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फॅक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu.

पत्रांक: -----

58/M/10

दिनांक: *2/5/18*

QUOTATION NOTICE

To,

M/s.....
.....
.....

The sealed quotation are invited for P/F of Nozzal swenack piller cock in Lab and other misc. work at Bio chemistry deptt. KGMU as given below. The detail of quotation notice can be seen at website www.kgmcindia.edu and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the undersigned duly marked on the envelope the number and date of this notice latest by 3.30p.m on dated *27/05/18*

Sl.No.	Particulars	Quantity	Unit	Rate
1	S/F C.P Nozzel swenack piller cock 15mm dia make of Parryware.	30.00	Nos	
2	S/F C.P Long body bib cock 15mm dia make of Parryware.	2.00	Nos	
3	S/F C.P Nozzel bib cock 15mm dia make of Parryware.	1.00	No.	
4	S/F C.P short body bib cock 15mm dia make of Parriware.	2.00	Nos	
5	P/F 2mm thick Pvc plain sheet for ceiling pitch up to including all labour material t&p etc. complete	8.35	Sqm	
6	Scraping old white or color wash including disposal of refuse as directed by engineer in charge.	180.00	Sqm	
7	Providing and laying cement based white putty of average thickness 0.60mm of approved band and manufacture, over the old painted wall surface to prepare the surface even and smooth complete.	180.00	Sqm	
8	Distempering with oil bound distemper two coat of approved brand old Surface to give an even shade including all material, labour T&P etc. complete.	380.00	Sqm	
9	Painting two coat with Supirior synthetic enamel paint in old Surface including supply of labour material t&p etc. complete.	22.50	sqm	
10	S/f of anodized aluminum sliding openable window with aluminum section 4x1-3/4x2" window panel and 5mm thick frosted glass including all. labour material t&p etc.	1.20	Sqm	
11	S/f anodized aluminum grill all including stainless steel wire gauze for including all labour material t&p etc.up to proper complete of work	1.20	Sqm	
12	S/F of anodized aluminum fixed partition in section 4"x1-3/4" x 2.00 "mm without glass including all. labour material t&p etc.	0.20	Sqm	
13	P/L of A.C 6mm thick corrugated sheets (As per IS:14871) roofing up to any pitch and fixing with polymer coated J, or L hooks.bolt and nuts 8mm dia.	4.68	Sqm	
14	Mild steel or iron work of small sizes and sections such as holding down bolts, hold fast, tie, rods gratings, etc.	40.00	kg	



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu.

पत्रांक: -----

दिनांक:-----

	including supply of steel, bolts nuts etc. & ther fixing required for proper compleiteion of the work.			
15	N-Trap joint Tile is removed or dismantled Then area under works is uncovered and cleaned by unstable or volatile chemical. Cleaned area is repaired by filling /honeycomb covering and chemical putty then treaed with 1 layer of ISo 117 Cr. Then 1ft or 1.5ft pipe is set as per the required height and level. After pipe is set 2 nd layer of ISo 117 Cr is applied for its covering.	2.00	Nos	

Term & Condition

1. G.S.T shall be applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.

Yours faithfully

(Dinesh Kumar Raj)
Executive Engineer

No. 59-13/M/10
of DT.

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Dr. Sandeep Bhattacharya, Faculty Incharge, Website Administratiion Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date.....
To: 02/05/18 to 09/05/18
3. Sri Anjani Kumar, Assistant Engineer, Works deptt. K.G.M.U.U.P.Lucknow
4. Sri T.C Yadv, Junior Engineer, Works deptt. K.G.M.U.U.P.Lucknow
5. Notice Board.

(Dinesh Kumar Raj)
Executive Engineer