



किंग जार्ज चिकित्सा विश्वविद्यालय २०प्र०, लखनऊ- 226003
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu.

पत्रांक: -----

54/110

दिनांक: 28/01/19

QUOTATION NOTICE

The sealed quotation are invited for Painting and repairing cold room and outer area of Murchery deptt. KGMU from the registered contractor of KGMU the detail of quotation notice can be seen at website www.kgmcindia.edu and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated .a.s./a.2/19
Detail of the works as given below-

S.No.	Particulars	Quantity	Unit	Rate
1.	Dismantling existing old plaster including disposal of refuse as directed by engineer incharge.	16.67	Sqm	
2	Dismantling cement concrete or granolithic floors, including stacking of dismantling material as per direction by the E /In charge.	11.55	Sqm	
3	M-150 class 120mm thick brick work in 1:4 cement & coarse sand in super structure including supply of all materials, labours and T&P etc.for proper completion of the work.	0.39	Cum	
4	M-150 class 230mm thick brick work in 1:4 cement & coarse sand in super structure including supply of all materials, labours and T&P etc.for proper completion of the work.	0.46	Cum	
5	P/L cement concrete in 1:2:4 cement, coarse sand 20mm stone grit.	0.50	Cum	
6	P/L PCC 1:6:12 cement, fine sand& 40mm brick	2.50	Cum	
7	P/L RCC Plat form in 1:2:4 cement, coarse sand & 20mm stone grit.	0.03	Cum	
8	Mild steel work for reinforcement in plain cement concrete.	6.24	Kg	
9	40mm thickness flooring 1:2:4 cement coarse sand stone aggregate of with floating coat of neat cement.	11.55	Sqm	
10	P/L of appd. Quality 80mm thick unipaver (Zig-Zag) rubber molding interlocking tiles notless than 30MPa including leveling and dressing of surface to required level and slope, filling joints local sand and also including the cost of all material, labour T&p complete.	5.12	Sqm	
11	Laying old cement cocncrete interlocking tiles colour and pattern over and including 50mm thick compacted filling with jointes fine sand etc. complete.	5.87	Sqm	
12	S/L of pavit tiles 300x300mm over 20mm base of 1:4 cement coarse sand complete.	1.48	Sqm	
13	P/L 12mm cement plaster in 1:6 on wall with cement and coarse sand including supply of all material labour and T&p etc. for proper completion of the work.	19.96	Sqm	
14	S/F of anodized aluminum fixed partition in section 4"x1-3/4" x 2.00" mm with 5mm thick frosted glass including all. labour material t&p etc.	2.74	Sqm	
15	P/L one coat white cement of approved quality on new surface.	924.54	Sqm	

54/110
28/01/19



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu.

पत्रांक:

			दिनांक:.....	
16	Providing and laying white cement based putty of average thickness 1mm of approved band on new surface.	19.96	Sqm	
17	Scraping old white or color wash including disposal of refuse as directed by engineer in charge.	74.46	Sqm	
18	Providing and laying cement based white putty of average thickness 0.60mm of approved band and manufacture, over the old painted wall surface to prepare the surface even and smooth complete.	54.50	Sqm	
19	Distempering with oil bound distemper two coat of approved brand old Surface to give an even shade including all material, labour T&P etc. complete.	122.93	Sqm	
20	Painting two coat with Superior synthetic enamel paint in old Surface including supply of labour material t&p etc. complete.	58.20	Sqm	
21	S/F 10 Lit PVC low down cistern for appd. Quality in completed.	1.00	Nos	
22	S/F of PVC waste pipe for wash basin/sink.	3.00	Nos	
23	Plumber with helper for fitting of sanitary item.	1.00	Nos	
24	Providing Carpenter with helper for repairing of old door/window.	1.00	Nos	
25	S/f Ball valve 25mm dia NMC.	2.00	Nos	
26	Providing labours for Clearing of Site.	4.00	Nos	

Term & Condition

1. G.S.T & Labour cess shall be applicable as per rules.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotations are liable to be rejected.
5. The undersigned reserve the right to reject quotations in part or whole without assigning any reason.


Yours faithfully


(Dinesh Kumar Raj)
Executive Engineer

No. 547-51/M10 of DT.

Copy for information and necessary action to:-

6. Registrar, King George's Medical University U.P, Lucknow.
7. Dr. Sandeep Bhattacharya, Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date 28/1/19 To 28/1/19.
8. Sri Suresh Kumar, Assistant Engineer, Works deptt. K.G.M.U.U.P.Lucknow
9. Sri T.C Yadv, Junior Engineer, Works deptt. K.G.M.U.U.P.Lucknow
10. Notice Board.


(Dinesh Kumar Raj)
Executive Engineer