

**WORKS DEPARTMENT, KING GEORGE'S MEDICAL UNIVERSITY
U.P, LUCKNOW**

No. 5502
M-10

of dt. 27/11/18

Quotation Notice

Sub:- Tile, Painting & other Misc civil work, P.R.O Room Deptt of Lari Cardiology

Dear sir,

Please quote your rates for the above work as per specifications given below. The sealed quotations should reach to undersigned duly marked on the envelope the number and date of this notice latest by 3:30 P.m on dated 25/12/18

Sl.No	Particular	Quantity	Unit	Rates
1	Dismantling of Existing old plaster	21.20	Sqm	
2	Providing and laying Vitrified tiles in floor with different sized(thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade laid with cement based high ploymer modified quick set tile adhesive(water based) conforming to IS:15477, in average 6mm. thickness, including grouting of joints (Payment for grouting of joints to be made separately) (Size of tile 600x600mm)	6.80	Sqm	
3	P/L Kajaria or equivalent wall tiles 300x600mm. with water absorption less than 0.08% and conforming to IS:15622 of approved make in all colours and sheds, lied on 20mm. thick cement mortar in 1:4 cement and coarse send including grouting of joints with white cement matching pigment.	21.20	Sqm	
4	Scraping of colour white wash old surface.	46.70	Sqm	
5	P/L of Birla white putty for making good smooth surface.	46.70	Sqm	
6	Oil bound distemper in two coat.	12.90	Sqm	
7	Application of two coats Apex. Altima paint of Approved Brand on old Surface Given an even Shade including supply of all material, labour T&P as required for proper completion of work	33.80	Sqm	
8	Enamel painting in two coat	4.70	Sqm.	

Terms & Condition

1. The quotation should be accepted by Registered Contractor of KGMU.
2. The rates should be quoted excluding G.S.T. & Labuor Cess.
3. The work will completed within given time in the work order.
4. The quotation should be reached by Registered post upto date mentioned in quotation.

Yours Faithfully

Ram Velas Verma

(Ram Velas Verma)
Executive Engineer