



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

निर्माण विभाग (सिविल सेक्शन)

फोन (मुख्यालय कार्यालय) : 0522-2257540 फेक्स : 0522-2257539 वेबसाइट : www.kgmcindia.edu

पत्रांक: 4444/M10

28/09/18

QUOTATION NOTICE

To,

M/s.....

.....


The sealed quotations are invited for P/L RCC Slab for Pump room & Other misc. civil work at Kalam Center KGMU from the registered contractor of KGMU. The detail of quotation notice can be seen at website www.kgmcindia.edu and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 05/10/18.

Detail of the work as given blow-

Sl.No.	Particulars	Qty	Unit	Rate
1.	M-150 class 230mm thick brick work in 1:4 cement & coarse sand in super structure including supply of all materials, labours and T&P etc.for proper completion of the work.	0.45	Cum.	
2.	M-150 class 120mm thick brick work in 1:4 cement & coarse sand in super structure including supply of all materials, labours and T&P etc.for proper completion of the work.	0.14	Cum.	
3.	P/L RCC work in 1:2:4 cement, coarse sand and 20mm grit stone for lintel including necessary centering and shuttering & also including supply of all materials , labours and T&P etc complete.	0.07	Cum.	
4.	P/L RCC work in 1:2:4 cement, coarse sand and 20mm grit stone for slab including necessary centering and shuttering & also including supply of all materials , labours and T&P etc complete.	1.00	Cum.	
5.	P/L RCC work in 1:2:4 cement, coarse sand and 20mm grit stone for beam including necessary centering and shuttering & also including supply of all materials , labours and T&P etc complete.	0.32	Cum.	
6.	Mild steel work for reinforcement in plain concrete work including cutting,bending and binding complete.	124.09	Kg.	
7.	Fabrication of m.s door with m.s angle 30x30x5mm , 35x35x6mm , m.s flat 30x5mm, 20x4mm ,m.s sheet 16 gauge with m.s chaukhat including all material and labour T&P etc complete.	62.83	Kg.	
8.	S/F m.s hinges 100mm long.	4.00	Nos.	
9.	S/F m.s handle 150mm long.	2.00	Nos.	
10.	S/F m.s sliding bolt 16mm dia & 250mm long.	2.00	Nos.	
11.	12mm cement plaster in 1:6 in single coat on wall with cement and coarse sand including supply of all materials, labours and T&P etc.for proper completion of the work.	11.10	Sqm.	
12.	12mm cement plaster in 1:4 in single coat on ceiling with cement and coarse sand including supply of all materials, labours and T&P etc.for proper completion of the work.	8.08	Sqm.	
13.	P/L 20mm cement plaster in 1:3 cement,coarse sand with floating coat of neat cement.	8.38	Sqm.	

28/09/18

[Signature]



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

निर्माण विभाग (सिविल सेक्शन)

फोन (कुलसचिव कार्यालय) : 0522-2257540 फॅक्स : 0522-2257539 वेबसाइट : www.kgmcindia.edu.

पत्रांक:...../.....

14.	P/L of birla white putty for making good and smooth surface on new surface.	19.24	Sqm.	
15.	P/L of birla white putty for making good and smooth surface on old surface.	51.86	Sqm.	
16.	Distemping with oil bound distemper two coat of approved brand on decorated wall surfaces togive an even shade including all materials, labours T&P etc. complete .	29.92	Sqm.	
17.	Application of two coats apex ultima paint on outer surface of wall including one coate white cement wash on new surface/other coated surface and supply of all materials, labours and T&P etc for proper completion of the work.	41.13	Sqm.	
18.	Painting 2coat with superior synthetic enamel paint including one coat primer on new surface over 10 cm width or girth	4.03	Sqm.	
19.	Painting 2coat with supior synthetic enamel paint on previously painted old surface over 10 cm width or grith.	6.86	Sqm.	
20.	S/I anodized aluminium fixed partition in section 4"x1-3/4" with 5mm thick plain/frosted glass.	4.50	Sqm.	
21.	S/I anodized aluminum grill all including stainless steel wire gauze for including all labour material t&p etc.up to proper complete of work	4.50	Sqm.	

Term & Condition

1. G.S.T & Labour Cess shall be applicable as per rules .
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully



(Dinesh Kumar Raj)
Executive Engineer

No. 11445-119/M/L of dt.

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Dr. Sandeep Bhattacharya, Faculty Incharge, Website Administration, Data Center, P.I.I Bhawan, KGMU for Uploading the quotation Notice in KGMU. Website from date 28/09/18 to 25/10/18...
3. Sri Anjani Kumar Assistant Engineer, Works deptt. K.G.M.U.U.P.Lucknow
4. Sri T.C Yadav, Junior Engineer, Works deptt. K.G.M.U.U.P.Lucknow
5. Notice Board.


(Dinesh Kumar Raj)
Executive Engineer