



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003
निर्माण विभाग (सिविल सेक्शन)

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522-2257539 वेबसाइट : www.kgmcindia.edu.

पत्रांक 2773
K/M/10

25/07/18

QUOTATION NOTICE

To,

M/s.....

.....

The sealed quotations are invited for Repairing & Painting work for H.O.D Room, Attached room & Front Outer Painting of Pathology Department at KGMU. from the registered contractor of KGMU. The detail of quotation notice can be seen at website www.kgmcindia.edu and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the undersigned by registered post duly marked on the envelope the number and date of this notice latest by dated 25/07/18. Detail of the work as given blow-

Sl.No	Particulars	Qty	Unit	Rate
1.	Dismantling existing plaster including disposal of refuse as directed by the Engineer-in-charge with in a distance of 60 metre.	36.01	Sqm.	
2.	Dismantling of old damage tiles including of dismantled materials as directed by Engineer-in-charge.	1.93	Sqm.	
3.	12mm cement plaster in 1:6 in single coat on wall with cement and coarse sand including supply of all materials, labours and T&P etc.for proper completion of the work.	36.01	Sqm.	
4.	P/L floor tiles 300x300mm of appd. Quality over 20mm thick cement mortar 1:4 cement and coarse sand.	1.93	Sqm.	
5.	P/L wall tiles 300x300mm of appd. Quality over 20mm thick cement mortar 1:3 cement and coarse sand.	10.59	Sqm.	
6.	P/L of cement based putty for making good and smooth surface on new surface.	36.01	Sqm.	
7.	Scraping old white or colour wash including disposal of refuse material as directed by Engineer-in-charge with a distance as distance of 60 met.	352.30	Sqm.	
8.	P/L of cement based putty for making good and smooth surface on old surface.	352.30	Sqm.	
9.	Distempering with oil bound distemper two coat of approved brand on decorated wall surfaces to give an even shade including all materials, labours T&P etc. complete.	392.86	Sqm.	
10.	Application of two coats apex ultima paint on outer surface of wall including one coate white cement wash on new surface/other coated surface and supply of all materials, labours and T&P etc.for proper completion of the work.	190.43	Sqm.	
11.	Painting 2coat with superior synthetic enamel paint on previously painted old surface over 10 cm width or grith.	77.63	Sqm.	
12.	S/f PVC pipe 15mm dia.	7.30	Rmt.	
13.	S/f C.P jet spray (butterfly shape) with 1metre long connection tube of Prayag make or equivalent.	1.00	Nos.	
14.	S/F pvc connection 450mm ling with two brass units.	3.00	Nos.	
15.	S/F C.P one way angle valve 15mm dia.	3.00	Nos.	
16.	S/F pvc waste pipe 32mm dia 600mm long.	1.00	Nos.	
17.	S/F CP floor jaali.	1.00	Nos.	
18.	Fixing Panes of glass 4mm thick with equal or equivalent I.S.I. marked quality and including putty, brads, springs etc complete.	0.76	Sqm.	



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003
निर्माण विभाग (सिविल सेक्शन)


फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522-2257539 वेबसाइट : www.kgmcindia.edu.

पत्रांक:...../

Term & Condition

- 1 G.S.T shall be paid and or deducted as per rules applicable.
- 2 The work will be completed within given time.
- 1 Quantity can be increase or decrease as per requirements.

Yours faithfully



(Dinesh Kumar Raj)
Executive Engineer




2724-78/M-1 c
No...../ of dt.

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Dr. Sandeep Bhattacharya, Faculty Incharge, Website Administration, Data Center, P.H.I Bhawan, KGMU for Uploading the quotation Notice in KGMU. Website from date 25/7/18 to 01/12/18
3. Sri Anjani Kumar Assistant Engineer, Works deptt. K.G.M.U.U.P.Lucknow
4. Sri T.C Yadav, Junior Engineer, Works deptt. K.G.M.U.U.P.Lucknow
5. Notice Board.


(Dinesh Kumar Raj)
Executive Engineer