



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu.

पत्रांक: 4364/M/10

दिनांक: 27/09/18

QUOTATION NOTICE

The sealed quotation are invited for Repair painting work and other misc. work in Basement at Microbiology deptt. KGMU from the registered contractor of KGMU the detail of quotation notice can be seen at website www.kgmcindia.edu and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the undersigned by registered post duly marked on the envelope the number and date of this notice latest by dated 27/09/18
Detail of the works as given below-

Sl.No.	Particulars	Quantity	Unit	Rate
1.	Dismantling cement concrete or granolithic floors, including stacking of dismantling material as per direction by the E/L.	2.00	Sqm	
2.	P/L vitrified floor tiles in different sizes (thickness to be specified by the manufacture) with water absorption less then 0.08% and conforming to IS: 15622 of approved make in all colours and sheds , laid on 20mm thick cement mortar in 1:4 cement coarse sand including grouting of jointes with white cement and matching pigment etc. complete.	2.00	Sqm	
3.	Fabrication of M.S. grill for window including supply of all materials, labours and T&P etc.for proper completion of the work.	20.50	Kg	
4.	S/F pre painted galvanized iron ridge Jindal /Tata make ISI 450.mm wide including all material, labor t&p etc. complete	0.90	Rmt	
5.	Providing & fixing glass panes with putty and glazing clips in steel doors, windows, clerestory windows, all complete with 4mm thick glass panes.	1.25	Sqm	
6.	S/f of masquito proof m.s wire gauze on window with wooden beading.	3.50	Sqm	
7.	S/F of appd. Quality door closer. (Godrej)	3.00	Nos	
8.	Scraping old white or color wash including disposal of refuse as directed by engineer in charge.	615.75	Sqm	
9.	Providing and laying cement based white putty of average thickness 0.60mm of approved band and manufacture, over the old painted wall surface to prepare the surface even and smooth complete.	615.75	Sqm	
10.	Distempering with oil bound distemper two coat of approved brand old Surface togive an even shade including all material, labour T&Petc.complete.	615.75	Sqm	
11	Painting two coat with Supirior synthetic enamel paint in old Surface including supply of labour material t&p etc. complete.	25.90	Sqm	



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmciindia.edu.

पत्रांक: -----

दिनांक:.....

Term & Condition

1. G.S.T & Labour cess shall be applicable as per rules.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully

(Dinesh Kumar Raj)
Executive Engineer

No. 4365-69/MCO
of DT.

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Dr. Sandeep Bhattacharya, Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date 27/9/18 To 24/10/18.....
3. Sri Anjani Kumar, Assistant Engineer, Works deptt. K.G.M.U.U.P.Lucknow
4. Sri T.C Yadv, Junior Engineer, Works deptt. K.G.M.U.U.P.Lucknow
5. Notice Board.

(Dinesh Kumar Raj)
Executive Engineer