

WORKS DEPARTMENT, KING GEORGE'S MEDICAL UNIVERSITY
U.P, LUCKNOW

No. 1261/M-10

of dt. 30/05/18

Quotation Notice

Sub:- Providing Drain/Nali for Rain water near Lift & Floor tile work at Hospital Main Building GMAH.

Dear sir,

Please quote your rates for the above work as per specifications given below. The sealed quotations should reach to undersigned duly marked on the envelope the number and date of this notice latest by 3:30 P.m on dated 07/06/18

Sl.No	Particular	Quantity	Unit	Rates
1	Earth work in Excavation in trench for foundation.	8.64	Cum	
2	Providing and laying Cement concrete 1:6:12 (1 cement:6 fine sand : 12 graded brick aggregate 40 mm.nominal size) including supply of all material, labour and T&P etc. required for proper completion of the work and curing complete also including cost of formwork in foundation & floors.	0.86	Cum	
3	Class-150 Brick work 1:4 cement C-Sand in wall for foundation (12c.m. thick)	2.80	Cum	
4	12mm thick plaster 1:3 cement C-Sand in wall.	21.60	Sqm	
5	R.C.C. Slab in 1:2:4 cement C-Sand stone aggregate.	0.85	Cum	
6	Mild steel work Fabrication Angle (40x6)	115.700	Kg	
7	40mm thick flooring 1:2:4 cement C-sand stone Aggregate of with floating coat of neat cement.	10.80	Sqm	
8	Providing and laying Vitrified tiles in floor with different sized(thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade laid with cement based high ploymer modified quick set tile adhesive(water based) conforming to IS:15477, in average 6mm. thickness, including grouting of joints (Payment for grouting of joints to be made separately) (Size of tile 600x600mm)	33.88	Sqm	
9	P/L of appd.quality Pavit floor tiles size 300x300mm. over 20mm. thick base of 1:3 cement coarse sand in complete.	4.70	Sqm	

Terms & Condition

1. The quotation should be accepted by Registered Contractor of KGMU.
2. The rates should be quoted excluding G.S.T. & Labuor Cess.
3. The work will completed within given time in the work order.
4. The quotation should be reached by Registered post upto date mentioned in quotation.

Yours Faithfully

(Ram Velas Verma)
Executive Engineer

No. 1261-66/M-10

Date.....

Copy for Information and necessary action to:

1. Registrar, K.G.M.U, U.P. Lucknow
2. Finance Officer, K.G.M.U, U.P. Lucknow
3. Chief Medical Superintendent, K.G.M.U, U.P. Lucknow
4. Dr. Sandeep Bhattacharya, Website Administration Finance & Contact, P.H.I Bhawan, KGMU for uploading the quotation Notice in KGMU.
5. Assistant Engineer, Works deptt. K.G.M.U, U.P. Lucknow
6. Junior Engineer, Works deptt. K.G.M.U, U.P. Lucknow
7. Notice Board.

(Ram Velas Verma)
Executive Engineer