



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu.

पत्रांक: 2996/M/10

QUOTATION NOTICE



दिनांक: 02/08/18

To,

M/s.....

The sealed quotation are invited for P/L Vitrified floor tiles and file cabinet including painting work in the office at Pathology deptt. KGMU From the registered contractor of KGMU the detail of quotation notice can be seen at website www.kgmcindia.edu and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the undersigned by registered post duly marked on the envelope the number and date of this notice latest by dated 09/08/18. Detail of the works as given below-

Sl.No.	Particulars	Quantity	Unit	Rate
1.	Dismantling cement concrete or granolithic floors, including stacking of dismantling material as per direction by the E/I.	17.39	Sqm	
2.	Dismantling existing old plaster including disposal of refuse as directed by engineer incharge.	7.81	Sqm	
3.	P/L vitrified floor tiles in different sizes (thickness to be specified by the manufacture) with water absorption less then 0.08% and conforming to IS: 15622 of approved make in all colours and sheds , laid on 20mm thick cement mortar in 1:4 cement coarse sand including grouting of jointes with white cement and matching pigment etc. complete.	20.34	Sqm	
4.	P/L kajaria or equivalent wall tiles 200x300mm with water absorption less then 0.08% and conforming to IS: 15622 of approved make in all colours and sheds, laid on 12mm thick cement mortar in 1:3 cement coarse sand including grouting of jointes with white cement and matching pigment.	4.86	Sqm	
5.	Scraping old white or color wash including disposal of refuse as directed by engineer in charge.	67.96	Sqm	
6.	Providing and laying cement based white putty of average thickness 0.60mm of approved band and manufacture, over the old painted wall surface to prepare the surface even and smooth complete.	67.96	Sqm	
7.	Distempering with oil bound distemper two coat of approved brand old Surface to give an even shade including all material , labour T&P etc. complete.	67.96	Sqm	
8.	Painting two coat with Supirior synthetic enamel paint in old Surface including supply of labour material t&p etc. complete.	8.51	Sqm	



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmciindia.edu.

क:

दिनांक:

9.	Providing & fixing glass panes with putty and glazing clips in steel doors, windows, clerestory windows, all complete with 4mm thick glass panes.	0.98	Sqm	
10.	Making wooden wardrobe cabinet Covered wide 1.5 fit hight 2.00fit and opnable shutter as per appd. Design made of 19mm thick plywood outer side laminated and in side primer with painting including hinges, magnet, handle, lock as per direction HOD/ E/I	56.00	Sqft	

Term & Condition

1. G.S.T shall be paid and or deducted as per rules applicable
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.


Yours faithfully


(Dinesh Kumar Raj)
Executive Engineer

No. 2997-3001/M/10
of DT.

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Dr. Sandeep Bhattacharya, Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date 22/08/18 To 29/08/18
3. Sri Anjani Kumar, Assistant Engineer, Works deptt. K.G.M.U.U.P.Lucknow
4. Sri T.C Yadv, Junior Engineer, Works deptt. K.G.M.U.U.P.Lucknow
5. Notice Board.


(Dinesh Kumar Raj)
Executive Engineer