



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003  
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu.

पत्रांक: 2115/170

दिनांक: 22/05/17

**QUOTATION NOTICE**

To,

M/s.....

.....  
.....

The sealed quotation are invited for Painting of Dr. Geetika Nanda & Sister Incharge room and Construction m.s. angle rack in room of sister incharge of O.T-2 at Ground floor in General Surgery deptt. KGMU the detail of quotation notice can be seen at website [www.kgmcindia.edu](http://www.kgmcindia.edu) and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated .....

Details of the work as given below-

Sl. No.	Particulars	Quantity	Unit	Rate
1.	Dismantling existing old plaster including disposal of refuse as directed by engineer incharge.	79.54	Sqm.	
2.	P/L 12mm cement plaster in 1:6 on wall with cement and coarse sand including supply of all material labour and T&p etc. for proper completion of the work.	68.19	Sqm	
3.	P/L 12mm thick cement plaster in 1:4 on Ceiling with cement and coarse sand including supply of all material labour and T&p etc. for proper completion of the work	11.35	Sqm	
4.	P/L cement concrete in 1:2:4 cement, coarse sand 20mm stone grit.	0.06	Cum	
5.	Fabrication of M.S work for frame welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	332.65	Kg.	
6.	P/L one coat white cement of approved quality on new surface.	79.54	Sqm	
7.	Providing and laying white cement based putty of average thickness 1mm of approved band on new surface.	79.54	Sqm	
8.	Scraping old white or color wash including disposal of refuse as directed by engineer in charge.	54.09	Sqm	

261



# किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

## निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu.

पत्रांक: .....

दिनांक: .....

9.	Providing and laying cement based white putty of average thickness 0.60mm of approved brand and manufacture, over the old painted wall surface to prepare the surface even and smooth complete.	54.09	Sqm	
10.	Distempering with oil bound distemper two coat of approved brand old Surface to give an even shade including all material , labour T&P etc. complete.	224.55	Sqm	
11.	Painting two coat with Superior synthetic enamel paint in old Surface including supply of labour material t&p etc. complete.	42.53	Sqm	

### Terms & Conditions.

1. G.S.T & Labour Cess shall be paid and or deducted as per rules applicable
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotaion are Liable to be rejected.
5. The undersigned reserves the right to reject quotaions in part or without assigning any reason.

Yours faithfully

(Dinesh Kumar Raj)  
Executive Engineer

No. .... of DT.

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Dr. Sandeep Bhattacharya, Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date. .... To. ....
3. Sri Suresh Kumar, Assistant Engineer, Works deptt. K.G.M.U.U.P.Lucknow
4. Sri T.C Yadav, Junior Engineer, Works deptt. K.G.M.U.U.P.Lucknow
5. Notice Board.

(Dinesh Kumar Raj)  
Executive Engineer