



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmciindia.edu.

पत्रांक: 2018/11/18

दिनांक 03/08/18

QUOTATION NOTICE

To,

M/s.....

.....

.....

The sealed quotation are invited for Repair and painting for pump house and work and other misc. work near I.C.T.C. building at Pathology deptt. KGMU From the registered contractor of KGMU the detail of quotation notice can be seen at website www.kgmciindia.edu and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the undersigned by registered post duly marked on the envelope the number and date of this notice latest by dated 10/08/18.....

Detail of the works as given below-

Sl.No.	Particulars	Quantity	Unit	Rate
1.	Dismantling existing old plaster including disposal of refuse as directed by engineer incharge.	70.69	Sqm	
2.	M-150 Class brick work 230mm thick in 1; 4 cement coarse sand in foundation. Including supply of all materials, labours and T&P etc.for proper completion of the work.	1.68	Cum	
3.	P/L R.C.C Cover/slab in 1:2:4 cement, coarse sand & 20mm stone grit.	0.52	Cum	
4.	Mild steel work for reinforcement in plain cement concrete.	52.00	Kg	
5.	P/F M.S door with frame of 40x40x6mm angle iron and 18 gauze M.S sheet all necessary fitting complete. Using flats 30x6mm for diagonal braces and central cross piece.	1.85	Sqm	
6.	Fabrication of M.S. grill for window including supply of all materials, labours and T&P etc.for proper completion of the work.	290.0	kg	
7.	S/F M.S 1mm gauze M.S sheet in all labour material complete.	1.80	Sqm	
8.	P/L 12mm cement plaster in 1:6 on wall with cement and coarse sand including supply of all material labour and T&p etc. for proper completion of the work.	64.50	Sqm	
9.	P/L 12mm thick cement plaster in 1:4 on Ceiling with cement and coarse sand including supply of all material labour and T&p etc. for proper completion of the work.	6.19	Sqm	
10.	20mm thick cement plaster 1:4 cement cement coarse sand backing coat 17mm finishing coat 3mm complete.	8.46	Sqm	
11.	P/L PCC 1:6:12 cement, fine sand & 40mm brick ballast.	0.93	cum	



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmucindia.edu.

पत्रांक: -----


दिनांक:.....

12.	40mm thickness flooring 1:2:4 cement coarse sand stone aggregate of with floating coat of neat cement	11.63	Sqm	
13.	P/L one coat white cement of approved quality on new surface.	70.69	Sqm	
14.	Providing and laying white cement based putty of average thickness 1mm of approved band on new surface.	70.69	Sqm	
15.	Distempering with oil bound distemper two coat of approved brand old Surface to give an even shade including all material , labour T&P etc. complete.	70.69	Sqm	
16.	Painting two coat with Superior synthetic enamel paint in old Surface including supply of labour material t&p etc. complete.	10.37	Sqm	
17.	Application of two coats Ultima apex paint on outer surface of wall including supply of all materials, labours and T&P etc.for proper completion of the work.	36.00	Sqm	
18.	Providing J.C.V machine with driver.	5.00	Nos	
19.	Sweeper per pair with tools for cleaning of main hole.	8.00	Nos	

Term & Condition

1. G.S.T shall be paid and or deducted as per rules applicable
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.


Yours faithfully


(Dinesh Kumar Raj)
Executive Engineer

No. 349-53/M/10 of DT.

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Dr. Sandeep Bhattacharya, Faculty Incharge, Website Administration Data Center, PH Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date 03/08/18 To 10/08/18
3. Sri Anjai Kumar, Assistant Engineer, Works deptt. K.G.M.U.U.P.Lucknow
4. Sri T.C Yadv, Junior Engineer, Works deptt. K.G.M.U.U.P.Lucknow
5. Notice Board.


(Dinesh Kumar Raj)
Executive Engineer