



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

निर्माण विभाग (सिविल सेक्शन)

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522-2257539 वेबसाइट : www.kgmcindia.edu.

पत्रांक: 257/M10

दिनांक: 14/01/2019

Quotation Notice

Sub:- Misc.Civil Aluminum. Painting & Other work, Emergency Medicine, Ground Floor, Trauma Center in K.G.M.U.U.P., Lko.

Please quote your rates for the above work as per specifications given below. The sealed quotations should reach to undersigned duly marked on the envelope the number and date of this notice latest by 3.30 P.M. on dated --

23/01/19

Sl.No	Particular	Qty	Unit.	Rates
1	Dismantling of old unserviceable flooring/Kota stone.	8.53	Sqm	
2	Dismantling of Existing old plaster	40.18	Sqm	
3	Dismantling doors and windows with chaukhats excluding hold fast including stacking of dismantled material as directed by Engineer-in-charge.	4.36	Sqm	
4	Dismantling Brick work or stone work in line are cement mortar and including stacking of maerial as directed by the Engineer-in-charge complete etc.	0.63	Cum	
5	Providing and laying Cement concrete 1:6:12 (1 cement:6 fine sand : 12 graded brick aggregate 40 mm.nominal size) including supply of all material, labour and T & P etc.	0.20	Cum	
6	S/F of C.I. pipe 100 mm dia.	9.63	Rmt	
7	S/F of G.I. pipe 15mm dia with fitting complete.	18.89	Rmt	
8	C.C. work in 1:2:4 cement C-Sand stone aggregate.	0.36	Cum	
9	Class-150 Brick work 230 mm thick wall in 1:4 cement and coarse sand in superstructure.	2.00	Cum	
10	S/F of PVC Pipe 100mm dia.	6.35	Rmt.	
11	S/F of Nahani Trap 100mm dia.	01	No.	
12	P.V.C. Tee 100mm dia	01	No.	
13	S/F P.V.C. Bib Cock (Prayag)	02	Nos.	
14	S/F P.V.C. angle valve 15mm dia.	04	Nos.	
15	S/F P.V.C. Connection 24"	04	Nos.	
16	S/F West Pipe 32mm	02	Nos.	
17	S/F of CP floor Jali 100mm dia	02	Nos.	
18	Providing and laying Vitrified tiles in floor with different sized (thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to IS: 15622, of approved brand & Manufacturer, in all colours and shade laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS: 15477, in average 6mm. thickness, including grouting of joints to be made separately) (Size of tile 600x600mm)	7.80	Sqm	

9	P/L Kajaria or equivalent wall tiles 300x600mm. with water absorption less than 0.08% and conforming to IS: 15622 of approved make in all colours and sheds, lied on 20mm. thick cement mortar in 1:4 cement and coarse sand including grouting of joints with white cement matching pigment.	39.50	Sqm	
---	---	-------	-----	--

Terms & condition

1. The quotation should be accepted by Registered Contractor of K.G.M.U.U.P., Lko.
2. The rates should be quoted excluding G.S.T. & Labour cess.
3. The work will completed within given time in the work order.
4. The quotation should be reached by Registered post upto date mentioned in quotation.

Your's Faithfully

Ram Velas Verma

(Ram Velas Verma)
Executive Engineer

Arjun

No. 258-63/M/10
of dt.

Copy for information and necessary action to:

1. Registrar, K.G.M.U, U.P. Lucknow.
2. Finance Officer, K.G.M.U, U.P. Lucknow.
3. Chief Medical Superintendent, Trauma Center K.G.M.U, U.P. Lucknow.
4. Dr. Sandeep Bhattacharya, Website Administration Finance & Contact, P.H.I. Bhawan, K.G.M.U. U.P. for uploading the quotation Notice in K.G.M.U, U.P. Lucknow.
5. Assistant /Junior Engineer, Works deptt. K.G.M.U, U.P. Lucknow.
6. Notice Board.

Ram Velas Verma

(Ram Velas Verma)
Executive Engineer

Arjun

SK