किंग जार्ज चिकित्सा विश्वविद्यालय उ0प्र0, लखनऊ– 226003
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 बेवसाइट : www.kgmcindia.edu.

पत्रांकः ----------591/MMo

दिनांकः.....27/05/2023

QUOTATION NOTICE

To,

M/s.....

.....

.....

The sealed quotations are invited for P/F of Aluminum grill ,Repairing of Aluminum doors and miscellaneous civil work at Pnc , Booked ward and private ward nurse room ,Queen marry hospital , KGMU.The details of quotation notice can be seen at website www.kgmcindia.edu and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 03/06/2023

Details of work as given below:-

S.No	Particulars	Quantity	Unit	Rate
1	Providing and fixing ISI marked flush door shutters conforming to IS: 2202 non decorative type, core of block board construction with frame at 1st class hard wood and well matched commercial 3 ply veneers on both faces of shutters: 30mm thick including ISI marked nickel plated bright finished MS piano hinges with necessary screws.	1.38	Sqm	
2	P/F Enamel painting in two coat.	14.76	Sqm	
3	P/F Aluminium door stoppers	22	Nos	
4	P/F of 10mm Tie rod for aluminum repair works.	14.70	Rmt	
5	L/C for repairing of old aluminum doors, windows or partitions including labour material complete in all respect.	16.48	Sqm	
6	P/F 5mm thick Glass panes in aluminum work for doors , windows, ventilators shutter and partitions etc with EPDM rubber neoprene gasket etc complete as per the architectural drawing and the direction of engineer-in-charge.	9.00	Sqm	
7	P/F American aluminium handle with screw 150mm long.	4	Nos	
8	P/F of S.S hinges 100mm long with stainless steel screw etc complete	5	Nos	
9	P/F anodized aluminum grill with stainless steel wire gauge including all labour, material T&P etc up to proper completion of the work	11.99	Sqm	
10	P/F of door closer for appd. Quality godrej or equivalent.	7	Nos	
11	P/F of CP brass angle valve for basin mixer point of approved quality conforming to IS :8931 15mm normal bore	4	Nos	
12	S/F of CP Elbow action bibcock of 15mm dia.	2	Nos	
13	P/F of C.P pillar cock 15mm dia of approved quality.	3	Nos	
14	P/F CP jali heavy quality	4	Nos	
15	PVC internal fitting of low level cistern ISI marked.	8	Nos	
16	Providing of concentrated Acid for removal of solid disposal in C.I drainage lines with cost of material , labour, T&P complete in all respect.	4	Ltr	
17	P/L ceramic floor tiles in size 300x300mm with water absorption less then 0.08% and conferming to IS: 15622 of approved make in all colours and sheds , laid on 20mm thick cement mortar in 1:4 cement coarse sand including grouting of joints with white cement and matching pigment etc. complete.	0.54	Sqm	
18	White glazed earthern ware (European type) W.C pan 505mm dia with seat cover of jaguar ESSCO, cera, hindware.	1	Nos	
19	S/F 10 lit PVC low down cistern for appd. Quality in complete.	1	Nos	
20	Welding plant with operator without rod and power for gate repairing	2	Nos	

किंग जार्ज चिकित्सा विश्वविद्यालय उ0प्र0, लखनऊ– 226003
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 बेवसाइट : www.kgmcindia.edu.

पत्रांक: ----------

दिनांक:.....

	opposite to gyne ward.			
21	Providing carpenter with helper for repairing of old door/window	6	Nos	
22	Semi skilled labour miscellaneous civil work.	4	Nos	
23	Providing plumber with helper repairing for old sanitation work.	3	Nos	
24	Sweeper per pair with tools.	3	Nos	

Terms & Conditions

31. G.S.T and labour cess shall be paid or deducted as per rules applicable.
32. The work will be completed within given time.
33. Quantity can be increase or decrease as per requirements.
34. Conditional quotations are liable to be rejected.
35. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully

(Dinesh Kumar Raj)
Executive Engineer

No...591/MU.../ of DT.

Copy for information and necessary action to:-

31. Registrar, King George's Medical University U.P, Lucknow.
32. Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date 27/5/2023 To 03/06/2023
33. Sri Shailendra Singh, Asistant Engineer, Works deptt. K.G.M.U.U.P.Lucknow
34. Sri Prateek Dubey, Junior Engineer, Works deptt. K.G.M.U.U.P.Lucknow
35. Notice Board.

(Dinesh Kumar Raj)
Executive Engineer