किंग जार्ज चिकित्सा विश्वविद्यालय उत्तर प्रदेश, लखनऊ
कार्यालय अधिशासी अभियन्ता (विद्युत / यांत्रिक)

पत्रांक : ई / 253/EE(E/m) **Urgent Quotation Notice** दिनॉक : 15/08/2023

Sub:- Providing of copper earthing of lights for ICCU at Lari Cardiology deptt., KGMU, Lko.

Sir,

Sealed quotations are invited hear by the reputed firms/electrical contractors for the following items in sealed envelope to the undersigned **in the interest of patient care/ institution** with in 5 days from the date of calling quotation :-

Sl. No.	Particulars of Work	Qty.	Rate	Amount in Rs.
1.	Supply and burying of safe earthing electrode T-19 Cu-copper coated, length 3000mm. outer pipe 48.4mm. x 3.2mm., inner pipe 26.9mm. x 2.6mm., terminal dia 12mm, coating 80-100 micron filled with crystalline conductive mixture (CCM) having anti corrosiye & conductive property with 50kgs. Activated soil (BFC) capable of reducing the soil resistivity with good mixture of retaining capacity along with 30cm. square C.I. frame with hinged cover & masonry housing complete in all respect. As per ps. no. 727(B)	02 Nos.		
2.	Supply and laying of earth wire 8SWG Copper wire As per ps. no. 722	18 Mtrs.		
			G. Total Rs.	

Terms & Conditions:-

1. G.S.T. extra as applicable.
2. All the works shall be completed within the given time period (as per work order).
3. Quantity may be increase or decrease as per requirements at site and payment shall be made accordingly.
4. All the works shall be carried out as per PWD specifications.
5. Payment shall be made after satisfactory completion of above works through Finance office only.
6. Contractor having experience in Electrical Department, KGMU UP, Lucknow can quote their rates.

Your's Faithfully

Executive Engineer (Electrical)
K.G.M.U.U.P., LUCKNOW.

No. ---------- of Dt. ----------

Copy for information and necessary action to:-

1. Dr. Richa Khanna, Faculty In-charge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the Quotation Notice in KGMU. Website from ----------
2. Notice board.

Executive Engineer (Electrical)
K.G.M.U.U.P., LUCKNOW.