



R-15-4-2021

1023

किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu.

2797/M-10

दिनांक: 13/4/2021

QUOTATION NOTICE

To,

M/s.....

The sealed quotations are invited for Repairing and painting work of Repair and Painting work of different rooms of microbiology lab, p/f MS rack for covid samples, enclosure of stair case by ms grill and other misc. work in basement of microbiology department for expansion of testing facilities for Covid 19. from the registered contractor of KGMU. The detail of quotation notice can be seen at website www.kgmcindia.edu and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated Details of the work as given below-

Sl.No.	Particulars	Qty.	Unit	Rate
1	Dismantling existing old plaster including disposal of refuse as directed by engineer incharge.	5.00	Sqm.	
2	Dismantling cement concrete or granolithic floors including base concrete and including stacking of dismantled materials as directed by E/I.	12.70	Sqm..	
3	P/L P.C.C 1:6:12 cement, fine sand & 40mm brick ballast.	1.03	Cum.	
4	M-150 Class brick work in 1:4 cement coarse sand in super structure. including supply of all materials, labours and T&P etc. for proper completion of the work.	0.16	Cum.	
5	M-150 Class brick work in 1:3 cement coarse sand in superstructure including supply of all materials, labours and T&P etc. for proper completion of the work.	1.25	Cum.	
6	P/L 12mm cement plaster in 1:6 on wall with cement and coarse sand including supply of all material labour and T&p etc. for proper completion of the work.	6.80	Sqm.	
7	P/L Pavit floor tiles in size 300x300mm with water absorption less then 0.08% and conforming to IS: 15622 of approved make in all colours and sheds, laid on 20mm thick cement mortar in 1:4 cement coarse sand including grouting of joints with white cement and matching pigment etc. complete.	16.00	Sqm.	
8	P/F 1mm thick M.S sheet door with frame of 40x40x6mm angle iron and 3mm M.S gusset plates at the junctions and corners all necessary fittings a complete including applying a priming coat of approved steel primer		Sqm.	
9	S/F of Swiss welded mesh 1"x1" to gauze with 20x5 flat iron beading including all material labor T&p complete.	10.30	Sqm.	
10	P/F Precoated galvanised iron profile sheets 0.50mm coated thickness with zinc coating 120mm grams per as per IS:277, in 240 mpa steel grade 5-7microns epoxy primer on both side of the sheet and polyster top coat 15-18 microns sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length up to 12 meter or as desired by engineer incharge.	4.50	Sqm.	

VOP
JE

निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu.

दिनांक:.....

S/F of plain glass 4mm thick with wooden beading.	0.30	Sqm.	
Providing and laying white cement based putty of average thickness 1mm of approved band on new surface.	6.80	Sqm.	
Scraping old white or colour wash etc.including disposal of refuse material as directed by Engineer-in-charge.	133.00	Sqm.	
Providing and laying cement based white putty of average thickness 0.60mm of approved band and manufacture, over the old painted wall surface to prepare the surface even and smooth complete.	98.00	Sqm.	
Distemping with oil bound distemper two coat of approved brand old Surface to give an even shade including all material , labour T&P etc. complete.	98.00	Sqm.	
Distemping with oil bound distemper one coat of approved brand old Surface to give an even shade including all material , labour T&P etc. complete.	132.00	Sqm.	
Painting two coat with Supirior synthetic enamel paint on old Surface including supply of labour material t&p etc. complete.	27.62	Sqm.	
Fabrication of MS rack and grill for covid sample.	230.00	Kg.	
Providing labour for cleaning of site	4	No.	

: & Conditions.

. G.S.T & Labour Cess shall be paid or deducted as per rules applicable.


. The work will be completed within given time.

. Quantity can be increase or decrease as per requirements.

. Conditional quotations are liable to be rejected.

. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully


(Dinesh Kumar Raj)
Executive Engineer

798-2802 of DT. 13/4/2021

Copy for information and necessary action to:-


Registrar, King George's Medical University U.P, Lucknow.

Faculty Incharge, Website Administratiion Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date.....To.....

Sri Anajni Kumar, Assistant Engineer, Works deptt. K.G.M.U.U.P.Lucknow

Sri T.C Yadav, Junior Engineer, Works deptt. K.G.M.U.U.P.Lucknow

Notice Board.


(Dinesh Kumar Raj)
Executive Engineer


JE