



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003
निर्माण विभाग

42



फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu.

क्र. 33/M10

दिनांक 05/01/2022

QUOTATION NOTICE

To,

M/s.....
.....
.....

The sealed quotations are invited for Providing water proofing treatment of C.I. pipe joints in duct near office of Trauma centre building. The details of quotation notice can be seen at website www.kgmcindia.edu and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 12/01/2022

Details of work as given below:-

S.No.	Particulars	Quantity	Unit	Rate
1.	Making the opening in brick masonry including dismantling in walls by cutting masonry and making good the damages to wall complete to match existing surface l/c disposal of mulba, rubbish to the nearest dumping ground, all complete as per direction of E/I.	1.61	Sqm.	
2.	M-150 class 120mm thick brick work in 1:4 cement & coarse sand in super structure including supply of all materials, labours and T&P etc. for proper completion of the work.	0.48	Sqm.	
3.	P/L 12mm cement plaster in 1:6 on wall with cement and coarse sand including supply of all material labour and T&p etc. for proper completion of the work.	0.48	Sqm.	
4.	P/L PCC 1:6:12 cement, fine sand & 40mm brick ballast.	0.16	Cum.	
5.	P/L 40mm thick cement concrete flooring with floating coat of neat cement in 1:2:4 cement, coarse sand 20mm stone grit.	1.63	Sqm.	
6.	Water proofing treatment for joints of C.I/PVC pipe with resin based water proofing chemical including fiber glass matt and fine powder width of chemical coating on joint not less than 250mm on any dia of pipe. Applying chemical coating on joint in three layers up to 3to 4mm thick and also including filling of gap between collar and pipe with resin based putty including fiber glass matt.	71	Nos.	
7.	Fabrication of M.S structure in openings of duct complete.	42.60	Kg.	
8.	S/F PVC pipe 100mm dia complete.	5.35	Rmt.	

Terms & Conditions

1. G.S.T and labour cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully

[Signature]