




किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu.



क्रमांक: 255/M10

दिनांक: 22/01/2022

QUOTATION NOTICE

To,

M/s.....

The sealed quotations are invited for Providing and fixing aluminium partitions including repairing of false ceiling in emergency holding area at trauma centre. The details of quotation notice can be seen at website www.kgmcindia.edu and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 22/01/2022

Details of work as given below:-

S.No.	Particulars	Quantity	Unit	Rate
1.	P/F Anodised aluminium work for doors with extruded built up standard tabular sections/ appropriate Z section and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/neoprene gasket etc	26.64	Kg.	
2.	P/F Anodised aluminium work for partitions with extruded built up standard tabular sections/ appropriate Z section and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/neoprene gasket etc	95.14	Kg.	
3.	L/C for removing, shifting and refixing of aluminium partitions including door shutters complete.	10.27	Sqm.	
4.	P/F float glass panes of 5mm thick in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber /neoprene gasket etc. complete as per directions of E/I.	6.88	Sqm.	
5.	P/F nova pan board in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber/neoprene gasket etc. complete as per the architectural drawings and the directions of E/I.	4.08	Sqm.	
6.	P/F anodized aluminium grill in aluminium partitions of approved quality including labour material T&P complete.	7.90	Sqm.	
7.	P/f American aluminium handle with screw 200 mm long.	04	Nos.	
8.	L/C for repairing of old damaged false ceiling.	27.53	Sqm.	

Terms & Conditions

1. G.S.T and labour cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any