



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu.

4657



पत्रांक: -----

7966/Mr

QUOTATION NOTICE

दिनांक: -----

21/12/2021

To,

M/s.....

The sealed quotations are invited for repairing and painting work of residence no.2A (Dr.S.P Jaiswar) at K.G.M.U from the registered contractor of KGMU. The detail of quotation notice can be seen at website www.kgmcindia.edu and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 28/12/2021.....

Details of the work as given below-

S.No.	Particulars	Quantity	Unit	Rate
1.	Dismantling existing old plaster including disposal of refuse as directed by engineer incharge.	67.64	Sqm.	
2.	P/L 12mm thick cement plaster in 1:4 on Ceiling with cement and coarse sand including supply of all material labour and T&p etc. for proper completion of the work.	13.90	Sqm.	
3.	P/L 12mm cement plaster in 1:6 on wall with cement and coarse sand including supply of all material labour and T&p etc. for proper completion of the work.	53.74	Sqm.	
4.	Scraping old white or colour wash etc.including disposal of refuse material as directed by Engineer-in-charge.	270.46	Sqm.	
5.	Applying one coat of water thinnable cement primer of approved brand on new wall surface.	67.64	Sqm.	
6.	Providing and laying white cement based putty of average thickness 1mm of approved brand on new surface.	67.64	Sqm.	
7.	Providing and laying cement based white putty of average thickness 0.60mm of approved band and manufacture, over the old painted wall surface to prepare the surface even and smooth complete.	270.46	Sqm.	
8.	Distempering with oil bound distemper two coat of approved brand on old Surface to give an even shade including all material, labour T&P etc. complete.	608.56	Sqm.	
9.	Painting two coat with Supirior synthetic enamel paint on old Surface including supply of labour material t&p etc. complete.	95.56	Sqm.	
10.	Providing labour for cleaning of site and collecting malwa.	02	Nos.	
11.	Cartage for disposal of malwa upto 10km away from the site.	5.43	Cum.	



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu.


पत्रांक:



दिनांक:.....

Terms & Conditions.

1. G.S.T & Labour Cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully



(Dinesh Kumar Raj)
Executive Engineer

 
JE A-E

No. 9967-71/MCO of DT.

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Dr. Richa khanna, Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date 2.11.2021 To 2.8.12.2021
3. Sri Anjani Kumar, Assistant Engineer, Works deptt. K.G.M.U.U.P.Lucknow
4. Sri T.C Yadav, Junior Engineer, Works deptt. K.G.M.U.U.P.Lucknow
5. Notice Board.


(Dinesh Kumar Raj)
Executive Engineer

 
JE A-E