



किंग जार्ज चिकित्सा विश्वविद्यालय २०१०, लखनऊ- 226003
निर्माण विभाग



फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu.

पत्रांक: 358/M10

QUOTATION NOTICE

दिनांक:.....

27/01/2022

To,

M/s.....
.....
.....

The sealed quotations are invited for Construction of guard room in front of new administrative block. The details of quotation notice can be seen at website www.kgmcindia.edu and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post of by hand duly marked on the envelope the number and date of this notice latest by dated 31/01/2022

Details of work as given below:-

S.No.	Particulars	Quantity	Unit	Rate
1.	Earth work in excavation in trenches for foundations in ordinary soil including lift upto 1.5 m. lead upto 50m and dressing of sides and rammings of bottom.	0.24	Cum.	
2.	P/L PCC 1:6:12 cement, fine sand & 40mm brick ballast.	0.04	Cum.	
3.	M-150 Class 230mm thick brick work in 1:4 cement coarse sand in foundation including supply of all materials, labours and T&P etc. for proper completion of the work.	0.57	Cum.	
4.	P/L cement concrete in 1:2:4 cement, coarse sand 20mm stone grit.	0.19	Cum.	
5.	P/L ceramic floor tiles in size 300x300mm with water absorption less than 0.08% and conforming to IS:15622 of approved make in all colours and sheds, laid on 20mm thick cement mortar in 1:4 cement coarse sand including grouting of joints with white cement and matching pigment etc. complete.	4.32	Sqm.	
6.	P/F precoated galvanised iron sheets 0.50mm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws with EPDM seal, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	25.80	Sqm.	
7.	Fabrication of M.S structure for shed with M.S. tube including material, labours, T&P complete.	340.44	Kg.	
8.	Painting 2 coats with superior synthetic enamel paint on new surface with one coat primer upto 10 cm width or grith.	7.14	Sqm.	
9.	Providing & fixing glass panes 5 mm thick with putty and glazing clips in steel doors, windows, clerestory windows, all complete.	2.34	Sqm.	
10.	P/F M.S. pressed butt hinges with screws complete.	08	Nos.	
11.	P/F M.S. sliding bolt of size 250x16mm with screws complete.	02	Nos.	
12.	Providing labour for cleaning site and collecting malwa.	04	Nos.	

Terms & Conditions

1. G.S.T and labour cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.

IPR
JE