



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003  
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu.

682/MSU

QUOTATION NOTICE

दिनांक: 11/02/2022

To,

M/s.....

The sealed quotations are invited for Repairing and painting work of toilet block including patchwork in verandah and rooms of new C.V. hostel. The details of quotation notice can be seen at website www.kgmcindia.edu and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 18/02/2022

Details of work as given below:-

S.No.	Particulars	Quantity	Unit	Rate
1.	Scraping old white or colour wash etc.including disposal of refuse material as directed by Engineer-in-charge.	414.95		
2.	Providing and laying cement based white putty of average thickness 0.60mm of approved brand and manufacture, over the old painted wall surface to prepare the surface even and smooth complete.	414.95		
3.	Distempering with oil bound distemper two coat of approved brand on old Surface togive an even shade including all material , labour T&P etc. complete.	644.78		
4.	Application of two coats apex Ultima paint on outer surface including supply of all materials, labours and T&P etc. for proper completion of the work.	24.62		
5.	S/F of Hepco red HCl pipe with socket including fitting 100mm dia.	2.40		
6.	Providing & fixing Stainless steel fly proof wire gauze to windows, clerestory windows & doors with M.S. Flat 15x3mm complete.	4.87		
7.	Fabrication of M.S railing with m.s. tubes including material labours T&P complete.	42.30		
8.	Painting 2 coats with supirior synthetic enamel paint on new surface with one coat primer upto 10 cm width or grith.	3.40		
9.	P/F of S.S hinges 100mm long with stainless steel screws etc. complete.	12		
10.	P/F internal fittings for PVC low level cistern.	04		
11.	S/F PVC waste pipe 32mm dia 600m long.	02		
12.	P/f Aluminium sliding door bolt with 16mm dia and 200mm long.	04		
13.	S/F aluminium tower bolt 150 mm long.	08		
14.	S/F PVC connection 600mm long Prayag make.	02		
15.	Providing labour for cleaning of site and collecting malwa.	02		

Terms & Conditions

1. G.S.T and labour cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Price may increase or decrease as per requirements.

Roy  
JE