

4619

18-12-21

U. LKO

किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu.

पत्रांक: 1868/M10

दिनांक: 17/12/21

QUOTATION NOTICE

To, M/s.....

The sealed quotations are invited for P/F collapsible steel shutter in office, marking in surgical holding area and other misc. work at trauma center building. The details of quotation notice can be seen at website www.kgmcindia.edu and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 24/12/21

Details of work as given below:-

S.No.	Particulars	Quantity	Unit	Rate
1.	Providing and fixing in position collapsible steel shutters with vertical channels 20x10x2 mm and braced with flat iron diagonals 20x5 mm size, with top and bottom rail of T-iron 40x40x6 mm, with 40 mm dia steel pulleys, complete with bolts, nuts, locking arrangement, stoppers, handles, including applying a priming coat of approved steel primer.	3.61	Sqm.	
2.	S/F swiss welded mesh 1"X1" gauge with 20x5mm flat iron beading including all materials, labours, T&P complete.	0.83	Sqm.	
3.	Painting 2 coats with superior synthetic enamel paint on new surface with one coat primer upto 10 cm width or grith.	9.86	Sqm.	
4.	Painting lines, dashes, arrows, etc. in two coats on new work with ready mix road marking paint including cleaning of surface of all dirt, dust and other foreign matter upto 10cm width.	7.41	Sqm.	
5.	P/L vitrified floor tiles in 600x600mm (thickness to be specified by the manufacture) with water absorption less then 0.08% and conforming to IS: 15622 of approved make in all colours and shades , laid on 20mm thick cement mortar in 1:4 cement coarse sand including grouting of jointes with white cement and matching pigment etc. complete.	4.32	Sqm.	
6.	P/L Pavit floor tiles 300x300mm over 20mm thick cement mortar in 1:4 cement coarse sand including grouting of jointes with white cement and matching pigment.	0.72	Sqm.	
7.	P/F float glass panes of 5mm thick in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubbe /neoprene gasket etc. complete as per directions of engineer-in-charge .	1.62	Sqm.	
8.	Fabrication of M.S structure for repairing of chawkhats complete.	22.40	Kg.	
9.	Providing labour charges for repairing of old aluminium doors.	12.60	Sqm.	
10.	S/F of appd quality door closer ISI marked. Godrej or equivalent.	06	Nos.	
11.	P/F C.P. elbow action bib cock of approved make complete.	04	Nos.	
12.	P/F brass spandal for pillar cock, bib cock of approved make complete.	12	Nos.	
13.	Providing welder with welding machine for fabrication.	06	Nos.	

Terms & Conditions

- G.S.T and labour cess shall be paid or deducted as per rules applicable.
- The work will be completed within given time.
- Quantity can be increase or decrease as per requirements.
- Conditional quotations are liable to be rejected.

18/12/21
JE

18/12/21
JE

18/12/21
JE